

SSC-263

(SL-7-7)

**STATIC STRUCTURAL CALIBRATION
OF SHIP RESPONSE INSTRUMENTATION SYSTEM
ABOARD THE SEA-LAND McLEAN**

This document has been approved
for public release and sale; its
distribution is unlimited.

**SHIP STRUCTURE COMMITTEE
1976**

SHIP STRUCTURE COMMITTEE

AN INTERAGENCY ADVISORY
COMMITTEE DEDICATED TO IMPROVING
THE STRUCTURE OF SHIPS

MEMBER AGENCIES:

United States Coast Guard
Naval Sea Systems Command
Military Sealift Command
Maritime Administration
American Bureau of Shipping

ADDRESS CORRESPONDENCE TO

Secretary
Ship Structure Committee
U.S. Coast Guard Headquarters
Washington, D.C. 20590

SR-211

1 0 300 1976

This report is one of a group of Ship Structure Committee Reports which describes the SL-7 Instrumentation Program. This program, a jointly funded undertaking of Sea-Land Service, Inc., the American Bureau of Shipping and the Ship Structure Committee, represents an excellent example of cooperation between private industry, regulatory authority and government. The goal of the program is to advance understanding of the performance of ships' hull structures and the effectiveness of the analytical and experimental methods used in their design. While the experiments and analyses of the program are keyed to the SL-7 Containership and a considerable body of data will be developed relating specifically to that ship, the conclusions of the program will be completely general, and thus applicable to any surface ship structure.

The program includes measurement of hull stresses, accelerations and environmental and operating data on the S.S. Sea-Land McLean, development and installation of a microwave radar wavemeter for measuring the seaway encountered by the vessel, a wave tank model study and a theoretical hydrodynamic analysis which relate to the wave induced loads, a structural model study and a finite element structural analysis which relate to the structural response, and installation of long term stress recorders on each of the eight vessels of the class. In addition, work is underway to develop the initial correlations of the results of the several program elements.

Results of each of the program elements will be published as Ship Structure Committee Reports and each of the reports relating to this program will be identified by an SL- designation along with the usual SSC- number. A list of all of the SL- reports published to date is included on the back cover of this report.

This report contains the results and a discussion of the calibration of the full-scale instrumentation and compares the results with calculated predictions.



W. M. Benkert

Rear Admiral, U. S. Coast Guard
Chairman, Ship Structure Committee

SSC-263

(SL-7-7)

Technical Report

on

Project SR-211, "SL-7 Data Collection"

STATIC STRUCTURAL CALIBRATION
OF SHIP RESPONSE INSTRUMENTATION SYSTEM
ABOARD THE SEA-LAND McLEAN

by

R. R. Boentgen and J. W. Wheaton
Teledyne Materials Research

under

Department of the Navy
Naval Ship Engineering Center
Contract No. N00024-75-C-4354

*This document has been approved for public release
and sale; its distribution is unlimited.*

U. S. Coast Guard Headquarters
Washington, D.C.
1976

ABSTRACT

This document reports the results of the calibration of the strain gage portion of the ship response instrumentation installed on the SEA-LAND McLEAN SL-7 class container ship. The calibration consisted of a succession of loading conditions achieved by selectively removing container cargo, and was performed on April 9-10, 1973 in Rotterdam. The measured stress changes are compared with calculated predictions, and the results are discussed. In general, the measurements and calculations agree substantially within tolerances assignable to physical conditions.

TABLE OF CONTENTS

	<u>Page</u>
I. INTRODUCTION	1
II. OBJECTIVE	1
III. CONCLUSIONS	1
IV. INSTRUMENTATION	2
General System	2
Scratch Gages	2
Additional Gages	3
Gage Locations	3
V. THE CALIBRATION EXPERIMENT	3
VI. RESULTS	4
VII. DISCUSSION	4
Rectangular Rosette Gages	5
Additional Gages	5
Transverse Girder	5
Forward Longitudinal Strain	6
Calculated Data	6
Longitudinal Vertical Bending	7
Scratch Gages	8
Torsional Shear Midship	8
Forward and Aft Sideshell Shear	9
VIII. GENERAL CONSIDERATIONS	9
IX. REFERENCES	10
TABLES I - X	11 - 47
FIGURES 1 - 16	48 - 67

LIST OF TABLES

	<u>PAGE</u>
I. SENSOR LIST -- 72/73 SEASON AND CALIBRATION	11
II. SENSOR AND SIGNAL NOMENCLATURE	16
III. SIGNAL DESCRIPTION AND RATIONALE	18
IV. ENVIRONMENTAL CONDITIONS AT CALIBRATION	22
V. OBSERVED DRAFTS	22
VI. CALIBRATION UNLOADING PLAN	23
VII. SUMMARY OF REDUCED STRAIN DATA	38
VIII. HATCH MEASUREMENTS	45
IX. CALCULATED BENDING MOMENTS, SHEAR FORCES, AND NORMAL STRESSES	46
X. ABS TORSIONAL MOMENTS FOR EACH HATCH AT EACH LOAD CONDITION	47

LIST OF FIGURES

1. INSTRUMENTATION FLOW DIAGRAM	48
2. GENERAL SENSOR LAYOUT	49
3. DETAILS OF STRAIN GAGE LAYOUT	50
4a-4d. CONTAINER LOADINGS, CONDITIONS 3, 4, 5, 6	51
5a-5f. CALCULATED LOADS VS. STATION, CONDITIONS 1, 3, 4, 5, 6, 7	55-56
6. STRESS VS. LOAD CONDITION, ROSETTES AR1 AND AR2	57
7. STRESS VS. LOAD CONDITION, ROSETTES R1 AND R2	58
8. REPRESENTATION OF STRAIN GAGE DATA, MIDSHIP TRANSVERSE GIRDER	59
9. LONGITUDINAL VERTICAL BENDING MIDSHIP (LVB) CHANGE IN MEASURED AND AND CALCULATED STRESS VS. LOAD CONDITION	60
10. LONGITUDINAL VERTICAL BENDING MIDSHIP (LVB) MEASURED STRESS VS. CALCULATED STRESS	61
11. LONGITUDINAL STRESSES (MIDSHIP) CALCULATED AND MEASURED DATA VS. LOAD CONDITION	62
12. COMPARISON OF DATA FROM SCRATCH GAGES AND LST GAGES	63
13. MEASURED TORSIONAL SHEAR MIDSHIP (TSM) AND LONGITUDINAL HORIZONTAL BENDING (LHB) AND CALCULATED TORSIONAL MOMENT VS. LOAD CONDITION	64

LIST OF FIGURES (Concluded)

	<u>PAGE</u>
14. STARBOARD BOXGIRDER SHEAR (MIDSHIP) CALCULATED AND MEASURED DATA VS. LOAD CONDITION	65
15. FORWARD SHEAR STRESS (SFP AND SFS) CALCULATED AND MEASURED DATA VS. LOAD CONDITION	66
16. AFT SHEAR STRESS (SAP AND SAS) CALCULATED AND MEASURED DATA VS. LOAD CONDITION	67

SHIP STRUCTURE COMMITTEE

The SHIP STRUCTURE COMMITTEE is constituted to prosecute a research program to improve the hull structures of ships by an extension of knowledge pertaining to design, materials and methods of fabrication.

RADM W. M. Benkert, USCG
Chief, Office of Merchant Marine Safety
U.S. Coast Guard Headquarters

Mr. P. M. Palermo
Asst. for Structures
Naval Ship Engineering Center
Naval Ship Systems Command

Mr. M. Pitkin
Asst. Administrator for
Commercial Development
Maritime Administration

Mr. K. Morland
Vice President
American Bureau of Shipping

Mr. C. J. Whitestone
Maintenance & Repair Officer
Military Sealift Command

SHIP STRUCTURE SUBCOMMITTEE

The SHIP STRUCTURE SUBCOMMITTEE acts for the Ship Structure Committee on technical matters by providing technical coordination for the determination of goals and objectives of the program, and by evaluating and interpreting the results in terms of ship structural design, construction and operation.

NAVAL SEA SYSTEMS COMMAND

Mr. C. Pohler - Member
Mr. J. B. O'Brien - Contract Administrator
Mr. G. Sorkin - Member

U.S. COAST GUARD

LCDR E. A. Chazal - Secretary
CAPT C. B. Glass - Member
LCDR S. H. Davis - Member
LCDR J. N. Naegle - Member

MARITIME ADMINISTRATION

Mr. N. Hammer - Member
Mr. F. Dashnaw - Member
Mr. F. Seibold - Member
Mr. R. K. Kiss - Member

MILITARY SEALIFT COMMAND

Mr. D. Stein - Member
Mr. T. W. Chapman - Member
Mr. A. B. Stavovy - Member
CDR J. L. Simmons - Member

NATIONAL ACADEMY OF SCIENCES SHIP RESEARCH COMMITTEE

Mr. R. W. Rumke - Liaison
Prof. J. E. Goldberg - Liaison

AMERICAN BUREAU OF SHIPPING

Mr. S. G. Stiansen - Chairman
Mr. I. L. Stern - Member
Dr. H. Y. Jan - Member

SOCIETY OF NAVAL ARCHITECTS & MARINE ENGINEERS

Mr. A. B. Stavovy - Liaison

WELDING RESEARCH COUNCIL

Mr. K. H. Koopman - Liaison

INTERNATIONAL SHIP STRUCTURES CONGRESS

Prof. J. H. Evans - Liaison

U.S. COAST GUARD ACADEMY

CAPT W. C. Nolan - Liaison

STATE UNIV. OF N.Y. MARITIME COLLEGE

Dr. W. R. Porter - Liaison

AMERICAN IRON & STEEL INSTITUTE

Mr. R. H. Sterne - Liaison

U.S. NAVAL ACADEMY

Dr. R. Bhattacharyya - Liaison

I. INTRODUCTION

The SEA-LAND McLEAN is the first in a class of eight high-speed (33 knot) containerhips. Each carries 200 forty-foot and 896 thirty-five-foot containers. In order to insure a rapid turnaround, the ships were designed with virtually unobstructed hatches running over 80% of the ship's length for loading of below-decks cargo. Such an arrangement, however, greatly reduces torsional stiffness and necessitates a revised structural layout.

Instrumentation of the vessel and collection of seaway response data by Teledyne Materials Research is part of a larger SL-7 program of model testing, structural analysis and data correlation between various tasks. Calibration of the strain gage sensors forms an integral part of the data collection and correlation tasks.

II. OBJECTIVE

The calibration event supplies two important factors necessary to the evaluation of seaway data.

1. Checkout of the Instrumentation System. The calibration was the first opportunity to check out the sense and magnitude of the installed gaging system against a deterministically varying load. Due to the complexity of the structure it is not always possible to make successful a priori decisions regarding gage locations. Unusual load paths, stress concentrations, interactions of applied loads, thermal environments, service conditions, modeling approximations, construction techniques, and other unpredictable conditions all may act to invalidate or reduce the desired effectiveness of applied instrumentation. Calibration, therefore, makes possible an overall check of the data system under a rational applied load.
2. Determination of Constants. The second and perhaps more important aspect of the calibration is that it provides data for the development of proportionality constants or influence coefficients between the applied load and the measured response. These factors can then be used to generate applied loads from the recorded seaway stresses.

Ideally, a calibration procedure seeks to apply sequentially a series of pure (single-component) loads while the specimen is at a uniform and constant temperature and free from other influencing factors or loads. These conditions were not fulfilled in the present calibration experiment due to various practical limitations. The limitations will be noted and the deviations from ideal conditions described in the appropriate succeeding sections.

III. CONCLUSIONS

The following general conclusions can be drawn based on the data gathered during the calibration experiment:

1. Measured changes in midship vertical longitudinal bending stress were consistently 80 percent of the calculated changes. Because of possible differences between the as-constructed and the theoretical (minimum-

scantling) section modulus upon which the calculations were based, this correlation is reasonable and indicates further that the load/response characteristic is linear and that data acquisition and reduction techniques do not contain any significant systematic errors.

2. Data have been reported relating response to applied loads, making possible the development of proportionality constants.
3. Stress levels achieved during the calibration are in most cases small relative to maximum measured seaway stress variations, and thermal conditions were not constant over the duration of the experiment. Extrapolations of loads by proportionality, therefore, should be undertaken with caution.
4. The maximum observed stress change for the calibrations loadings (10,200 psi, Sensor SY_A, during the torsion loading, Condition 4 to Condition 6) occurred at the starboard aft corner of Hatch No. 9, just forward of the Aft House. Other hatch corners at stations where hatch width changes are encountered exhibited high shear stresses near the stress relief cutouts. The hatch corners, therefore, are probably the most highly stressed parts of the structure.

IV. INSTRUMENTATION

General System. The sensors used in the calibration experiment were the identical ones used in the Fall/Winter 1972-73 seaway data collection program. A total of 105 discrete instrumentation channels are installed and were available for monitoring. Of these, 97 were strain gage sensors (including some multiple active element bridges designed to be sensitive to only specific types of loading), six were ship's motion (four linear acceleration and two rotational displacements), one was a multiplexed combination of ship operating parameters and one was assigned to a wave height radar. Only the strain gage sensors saw useful input levels during the calibration experiment. Table I contains a listing of all instrumentation sensors. It should be noted that the vertical bending stress is repeated on both recorders for matching purposes. For record keeping convenience, however, each of the five repeated monitorings (on Recorder No. 1 and on Recorder No. 2 in Modes A, B, C, and D) is assigned a separate sensor number. Table II lists abbreviations used for sensor nomenclature.

Figure 1 presents the overall instrumentation layout and signal flow as installed on the SEA-LAND McLEAN. All strain gages and ship motion sensors are first terminated in Intermediate Junction Boxes (IJB) positioned near the sensor location. All instrumentation is then routed to Junction Boxes (JB) installed by the ship's electrical contractors. Cabling for the data collection system is designated "612" throughout the ship. The majority of strain gage signals are fed directly from IJB's to JB's. Sensors Nos. 43 through 84 and 86 through 105 additionally pass through the Rosette Selection Box (RSB) and Girder Selection Box (GSB), respectively, where signals are selected and patched for recording. During the calibration, all available signals were patched and recorded for each loading condition. (For a more detailed definition of these gages and selection arrangement see Reference 1.)

Scratch Gages. All ships in the SL-7 series have a "scratch gage" mechanism installed in the starboard tunnel at midships for long-term monitoring. These self-contained gages are intended to record the maximum strain in the tunnel side

stringer on which they are mounted. In the McLEAN (only) two instruments are installed, one each port and starboard midships. Both instruments were manually advanced and recorded the strain at these locations for each calibration condition.

Additional Gages. Three additional gages, not available for analog monitoring during seaway runs, were installed for future reference. Located at the Aft House/Hatch 9 starboard cutout, these gages were read manually using a strain indicator during the calibration for Conditions 3 to 7.

Gage Locations. A short reference description of the location of all sensors is included in Table I. An expanded description and brief rationale for each sensor are presented in Tables II and III. Reflected in the gage layout is the realization that longitudinal vertical bending is the single most important operating parameter. Due to the unusually high speed of the ship, extensive ship motion sensors are incorporated to gather data on rigid-body motions. The majority of the remaining gages are located to ascertain the magnitude and effect of the torsional loading and distributions which are major considerations in the structural design. Such loadings tend to induce a fixed-end-bending type of deformation in the transverse girders and develop stress concentrations at hatch corners.

Figure 2 presents an overall plan of gage locations. Figure 3 presents installation details of the strain gage instrumentation.

V. THE CALIBRATION EXPERIMENT

The dockside calibration experiment was conducted on 9-10 April 1973 in Rotterdam, Holland. Originally the plan was to begin from a fully-loaded ship and selectively remove container cargo so as first to produce three increments of change in longitudinal vertical bending moment and then two torsional (twisting about a longitudinal axis) moment distribution increments. The initial (dockside) condition was designated No. 1, the five unloading increments described are Conditions Nos. 2 through 6, and the final (empty) condition is No. 7. Due to schedule constraints Condition No. 2 was deleted. For similar reasons a full set of zero readings at dockside (Condition No. 1) using all patching options was not possible. For this reason a previous condition, coming up the Maas River at slow speed, was defined as Condition Zero. All other measurements reported are referred to it unless otherwise noted. (Any other condition may be defined as Zero by algebraically subtracting the reading for that condition from all readings at the other conditions.)

Environmental conditions during the calibration are presented in Table IV, and the observed drafts are in Table V. Figures 4a-4d illustrate the changes in container loadings which are presented in Table VI. Figures 5a-5f present the calculated vertical bending moment, vertical shear force, and torsional moment distributions for each condition. Container unloading proceeded as described below:

Condition 1

Dockside initial readings were taken, no unloading, all channels and patch options were read by meter, tape recordings made on all modes but options not patched. (Note: Cargo holds beneath Hatch 3 and 10 were empty throughout the calibration.)

Condition 3 (Figure 4a)

Deck containers removed from Hatches 1 through 4 and 12 through 15. All op-

tions were read from meter and recorded on tape for this and subsequent conditions. This condition is the maximum decrease in hogging (vertical bending) moment.

Condition 4 (Figure 4b)

Remaining deck containers on Hatches 5 through 11 removed. This midship cargo removal results in an increase in hogging moment toward arrival level.

Condition 5 (Figure 4c)

Containers were removed from starboard side of Hatches 1 through 7, and the port side of Hatches 8 through 15, generating a torsional moment. After approximately one-half of the unloading was complete, Condition 5 was recorded. Hatch covers were placed asymmetrically to contribute to the torsional moment.

Condition 6 (Figure 4d)

Completion of unloading described in Condition 5. This is the maximum torsional load. It should be noted that this also changes the hogging moment component.

Condition 7

Nominally empty ship except for one propeller (47 long tons) loaded into Hatch 3 and one propeller in Hatch 4, all hatch covers on.

VI. RESULTS

As previously noted only strain gage sensors produced useful outputs during the calibration. A summary of all strain gage outputs, referenced to Condition Zero, is presented in Table VII. Single gage strains have been converted to stress by multiplying by Young's Modulus (E). In the case of three-arm rosette gages, calculated principal maximum (σ_1) and principal minimum (σ_2) stresses are also given along with the angular orientation to the principal axis as measured from the "A" or longitudinal gage. Changes in Hatch 7 dimensions were measured during the torsional part of the calibration, and are presented in Table VIII.

VII. DISCUSSION

The results of the calibration experiment fall into two classes depending upon whether or not the data can be predicted by theoretical calculations. Calculations of vertical bending moment, vertical shear force, and torsional moment were prepared by the American Bureau of Shipping from the loading information, but only a relatively small number of the sensors were designed to measure the effects of these basic loadings. The remainder of the strain gages were placed in areas of interest where calculations are difficult, and there are no specific predicted values available for comparison. The response of these gages to the applied loadings is, therefore, of great interest, and these results will be considered first. Figures have been prepared as noted to illustrate this discussion.

Rectangular Rosette Gages (Mounted Underdeck)

There is a great similarity in recorded strain (converted to stress) between geometrically comparable rosette elements located at Frames 226 and 258; R5 and R10; R6 and R11; R7 and R12; R8 and R13; R9 and R14. Although the gages at the more forward location show approximately 25 percent lower stress, the general changes with load are similar. This would be expected from the similar sections as the load decreases forward. Another decrease in stress is exhibited at the next forward location (Frame 290), but the response is modified due to the influence of the Forward House, especially in reducing the diagonal stresses. In this connection, the longitudinal stresses predominate in the tunnel at Frames 258 and 290, whereas the diagonal stresses predominate in the transverse girder near the hatch corners.

Figure 6 shows the output of each element of AR1 and AR2. These are located symmetrically on the port and starboard sides, respectively, at Frame 143 near the Hatch 9 corners just forward of the After House (see Figure 3). The opposite action of the torsional loading can be seen clearly here; the longitudinal and transverse elements exhibit nearly equal stress changes but in opposite directions. Similar behavior could not be expected in the case of the diagonal elements since these are tangent to the hatch corner cutout on the port side, but radial to the cutout on the starboard side. Note the relatively large tensile stress on the port (tangential side) diagonal indicating a stress concentration around this detail.

Figure 7 presents a similar representation for the R1 and R2 gages located port and starboard just aft of the Forward House, near the Hatch 1 corners. Since all the cargo used to apply the vertical bending and torsional moments was aft of this section, one might expect negligible stress changes. Relatively significant longitudinal stress changes are exhibited, however. These are associated more with the restraint of warping stresses than with the bending moment changes. Apparently, both the Forward and Aft Houses restrain the free action of the open cell torsional deflections, thus giving rise to significant (in comparison with those induced by vertical bending) longitudinal stress components. These components are especially important at hatch corners near the house structures because the house structure geometries further increase their magnitudes.

Additional Gages

Three additional gages (SY) were located circumferentially about the hatch corner reinforcement on the starboard side just forward of the Aft House (Hatch 9). The first of these gages, SYA, displayed the highest recorded strain change of any gage during the calibration. This gage was located 22 1/2 degrees from the longitudinal direction around the cutout ring. These gages were installed especially for the calibration, and were read with a strain indicator.

Transverse Girder (Normal Stresses)

Gages TGFS, TGMS, and TGAS were located in forward (Frames 242-244), mid (Frames 194-196), and aft (Frames 78-80) transverse girders, respectively. Each exhibited similar general responses which may be characterized as a change in bend-

ing stress distribution from vertical to horizontal as the loading conditions were varied from Conditions 1 to 6. The mid girder was the most heavily instrumented, with three normal stress gages in each side (one each at the corners and midpoint), one each at the top and bottom midpoint, and one shear installation at each side quarter point. Forward and aft transverse girders were instrumented only with normal strain gages near each side corner. (No readings were obtained from the aft transverse girder forward bottom corner gage, TGAS2, due to excessive zero offset.) Each gage set was mounted in a vertical plane about four feet inboard from the starboard tunnel--transverse girder interface. The change from the slow, steady ahead river condition (Condition Zero) to dockside (Condition 1) shows as a significant increase in vertical bending. In all cases, the change in stress distribution from Condition 1 to Condition 6 is characterized by a change from vertical to horizontal bending in the gage arrays, as shown in Figure 8. This is assumed to result from first the decrease in vertical bending and then the torsional warping of the hull cross sections. The former will result in upper fiber tension and lower fiber compression, since the reference condition is loaded, and unloading is the same as application of an upward load. The latter will result in tension in the aft fibers and compression in the forward fibers. Some of the distortion in the stress plots is probably due to the influence of the bulkhead on the aft side of each transverse girder section.

Shear stresses recorded at the upper section remain fairly constant while those at the lower quarter points tend to become increasingly negative, especially on the bulkhead side where a change in shearing stress of -6450 psi was recorded.

Forward Longitudinal Strain

Four single-element gages were located 12 inches below each longitudinal tunnel (port and starboard) and 12 inches above each tank top at Frame 290. Three of these gages exhibited fairly low stress (1,000 psi or less) with little response to bending loads and limited but definite torsional response. The fourth gage in the group (top, port) showed a large, linear increase in tensile strain between Conditions Zero and 3. Since there was no static load change between Conditions Zero and 1, there should have been no significant induced strain. Similarly, the load change between Conditions 1 and 3 should not cause the amount of tensile change indicated at this location. Additionally, the strain remains high through Condition 7. It must be assumed, therefore, that there was a warm-to-cool (coming up river/dockside shadow) thermal restraint stress induced at this location. The general response after Condition 4 is consistent with the loading conditions assuming an initial zero offset.

Calculated Data

The longitudinal vertical bending moments and the vertical shear forces were obtained from the ABS "Static Longitudinal Strength Calculation for SL-7 Sea-Land Containership Study" dated February 8, 1974 for the appropriate frame (see Figures 5a through 5f). The vertical bending moments were divided by the appropriate section modulus (top or bottom) taken from the Sea-Land Service, Inc. Containership Construction Center Drawing No. 10-097, "Section Moduli, Bending Moment (Cond. 7) and Bend. Stresses Curves", dated May 5, 1972. Using these

data the normal stresses were calculated by the relationship

$$S_b = \frac{M_b}{Z}$$

where S_b and M_b are the bending stress and bending moment, and Z is the section modulus at the section of interest. The results of the calculations are shown in Table IX.

The torsional moments at each hatch for each load condition were obtained from ABS calculations titled "SEA-LAND McLEAN Calibration Tests, Torsional Moments (Ton-Feet)", and are also plotted in Figures 5a through 5f. Summing these torsional moment contributions per hatch for each load condition along the ship length aft to forward, using the appropriate sign convention, produces an accumulative torsional moment per hatch for each load condition. These torsional moments are tabulated in Table X.

Longitudinal Vertical Bending

A comparison of measured and calculated values is presented in Figures 9 and 10. The tracking of the two sets of data against Condition is good in Figure 9, even though the absolute magnitudes are relatively low. Figure 10 demonstrates this relationship more clearly by plotting the measured values against the calculated ones. All of the points lie on a straight line having a slope of 0.8.

Figure 11 presents the longitudinal stresses measured top and bottom, port and starboard, at midship with the measured and calculated vertical bending stresses and the calculated torsional moments. These plots show the ship bending as the unloading proceeds from the slight hogging sense at Condition 1 to the greatest hogging sense at the unloaded Condition 7. In proceeding from Condition 1 to Condition 3, it is evident that the ship changes from a hogging sense toward a sagging sense. This result is reasonable, as in going from Condition 1 to Condition 3 containers are removed from the deck over Hatches 1-4 and 12-15, which tends to produce a more concentrated load at midship. Proceeding to Condition 4 shows a moment change back to a hogging sense. The hogging continues to increase to the unloaded Condition 7. This increase in hogging can be attributed to the fact that as the ship is unloaded the buoyant forces forward and aft decrease at a faster rate than at midship.

Detailed analysis of Figure 11 and the data in Table VII reveals some unexpected results, however, especially from the starboard neutral axis and bottom gages. Although the extreme fiber (top and bottom) gages respond in the expected sense for the two vertical bending conditions, the magnitude of change for the port and starboard gages, which should be approximately equal, in fact is considerably different. This indicates a nonuniformity of the bending moment across the section which is presently unexplained. Further, the relatively high stress changes indicated at the starboard neutral axis (not plotted) is also unexplained. This gage is located on the neutral axis approximately 24-3/4 feet above the base line, which, for the calibration, equals the draft shortly after Condition 4. In other words, this gage is at water temperature under one condition, and at approximately air temperature during the succeeding condition. Due to the inherent

self-temperature compensation of the strain gages used, thermally-induced strains will not be indicated. However, restraints of thermal strains are actual stresses and are indicated by the gage. Three types of thermally-induced stresses are possible for the calibration conditions: gross horizontal bending, gross vertical bending, and local stress changes across thermal interfaces (i.e., the waterline). Gross horizontal and vertical bending due to restraint of thermally-induced strains result in compressive stresses in the starboard side and deck, respectively, for the calibration condition of cool water and warm air/sun on the starboard side and deck. The large stress exhibited by the starboard neutral axis gage cannot be explained by these considerations. It is also interesting to note that this stress is largely maintained at Condition 7 (unloaded). As a result of this unexplained behavior, a physical check was performed on the installation. All circuits were found to be operating correctly and were correctly identified.

Scratch Gages

A scratch gage (a timer-advanced, peak-strain-reading, mechanical recording strain gage) has been installed in both longitudinal tunnels, midship, at the half-height side shell longitudinal stringer. (Other vessels in the SL-7 class have been fitted with one such gage each, in the starboard tunnel at a similar location.) Both recording charts were advanced manually at each calibration condition for recording peak strain. For the calibration experiment induced strains produced stylus deflections on the order of 0.020 inch, a quantity which is difficult to scale precisely. The plot of these stresses in Figure 12 also presents the corresponding outputs from the tunnel top stress gages near the same locations. Agreement between the two types of instrumentation is generally good, especially for the low stresses involved.

Torsional Shear Midship

In the absence of detailed sectional information suitable for calculating shear stresses using the calculated torsional moments, the moments themselves have been plotted in Figure 13 along with the measured shear data. The comparison is generally good. Virtually no output is indicated until the start of the torsional loading condition. Although there is no change in the horizontal bending sensor output for Conditions 1 through 4, an increasing output is indicated for Conditions 5 and 6. This corresponds to the torsional stress distribution (restraint of torsional warping resulting in symmetrically opposite normal stresses about the centerline and torsional neutral axis). It is also possible that some of this is due to thermally-induced horizontal bending which is restrained by the constant-temperature ship bottom.

Low outputs are exhibited by the two boxgirder (longitudinal tunnel) gages located on the tunnel top (deck) and bottom (see Figure 14). However, the indication is larger for the shear conditions and of opposite sign on top and bottom as would be expected due to the shear flow around the closed box section. The top gage on the starboard boxgirder appears to track fairly well with the calculated torsional moment. The bottom gage appears to be responding to shear associated with horizontal bending, which tends to reduce its response to the torsional moment. However, it is very difficult to relate calculated and measured data when the measured stresses are of such low magnitude.

Forward and Aft Sideshell Shear

One vertical shear sensor was installed on each sideshell neutral axis at Frames 289-290 and Frames 87-88 with each monitored separately. The forward pair (Figure 15) are located at the neutral axis and exhibited similar shear stresses, indicating that their response was associated principally with vertical bending loads. At the aft location (Figure 16) the gages were located above the neutral axis and exhibited similar but opposite behavior. A check of seaway data in head seas revealed that the Shear Aft Port transducer consistently produced data opposite in polarity from the Starboard data, indicating a polarity error in the bridge circuit. However, if horizontal bending and/or torsional loads were present, their effects could not be separated from vertical shear with transducers of this configuration. The shear stresses measured were very low in absolute magnitude.

VIII. GENERAL CONSIDERATIONS

Various factors present in the calibration experiment militate against more completely explainable results. Some of these are:

1. A clear, bright-sun day. Due to the ambient temperatures, the fact that the sun shone directly on the starboard side, and the almost 24-hour period required for the calibration, thermal effects from port to starboard, deck to waterline, and between day and night loading conditions resulted in appreciable strains. A determination of the magnitude of these strains is difficult for several reasons. First, the actual distribution of temperatures through material thicknesses and along various length and width dimensions is not known. From the temperature measurements made during the calibration (Table IV) a probable distribution may be assumed, but this may not be adequate. Second, the induced apparent strain depends on the degree of restraint of thermal expansion. (As mentioned previously, no response due to unrestrained thermal expansion is indicated by the gages employed. Evaluation of this problem requires a model analysis, and the exercise would become circular.
2. Schedule and other operational limitations. The original offloading plan called for an intermediate vertical bending condition (No. 2) which would have added another data point to indicate the linearity and correctness of the measured strains. Due to schedule considerations, this point was deleted. Further, due to the excessive time and labor which would have been required, a reverse torsional loading condition was not included in the original plan. This would have been useful in aiding the elimination of biased or nonsymmetrical loading behavior.
3. Low load level. Due to various logistical and other factors the ship arrived for the calibration experiment with less than a full cargo load. Most of the missing containers had been located fore and aft, resulting in a decreased change in hogging bending moment during the calibration. This situation contributed to the relatively low strain levels recorded. These low strain levels are, in many cases, of a magnitude similar to the thermal restraint stresses, built-in fabrication stresses, non-linear stresses due to structural nonuniformities and irregularities and/or zero offsets and drifts in the instrumentation. In many cases the load-induced stress levels are insufficient to rise above these

types of noise. However, the linearity of the vertical bending results provides considerable confidence in this important area.

4. Simultaneous variation in applied load. Ideally, during a calibration the various loads are varied individually so that the effect of each may be ascertained easily. During this calibration experiment it was not possible to achieve this ideal, primarily because the loading changes which induced a torsional response also caused changes in vertical bending moment. Such a situation makes it difficult to separate the cause (load) and effect (strain) relationship.

IX. REFERENCES

1. Fain, R. A. "Design and Installation of a Ship Response Instrumentation System Aboard the SL-7 Class Containership S.S. SEA-LAND McLEAN," Ship Structure Committee Report SSC-238 1973.
2. Fain, R. A., Boentgen, R. R., and Wheaton, J. W. "First Season Results from Ship Response Instrumentation Aboard the SL-7 Class Containership S.S. SEA-LAND McLEAN in North Atlantic Service," Ship Structure Committee Report SSC-264.

TABLE I
SENSOR LIST
72/73 Season and Calibration

Sensor No.	Sensor Name.	Location (2)		Config.	Orient	Sensitive to	Recorder	Channel	Mode	Full Cal	Units	Circuit No.
		Frame	Position									
1 (1)	LVB	186 $\frac{1}{4}$	Tunnel Top	Dyadic	Long.	V. Bend.	1	1	-	8214	PSI	1
2	ISM	186 $\frac{1}{4}$	Side N/A	Shear	Vert.	H.T. Shear	1	2	-	4991	PSI	3
3	Wave Ht.	300	Fwd Deckhouse (Stbd)	Radar	Anglud	Range(3)	1	3	-	3.6	Vert	-
4	Roll	178	26" Fwd 31' ATT	Pend.	Trans.	Roll	1	4	-	20	Deg.	-
5	Pitch	178	26" Fwd 31' ATT	Pend.	Long.	Pitch	1	5	-	20	Deg.	-
6	NAV	178	23" Fwd 31' ATT	Mass	Vert.	V. Accel.	1	6	-	1	R	-
7	NAV	178	23" Fwd 31' ATT	Mass	Trans.	V. Accel.	1	7	-	1	S	-
8	FAV	290	14" Fwd 59' ATT	Mass	Vert.	V. Accel.	1	8	-	1	R	-
9	FAT	250	14" Fwd 59' ATT	Mass	Trans.	V. Accel.	1	9	-	1	S	-
10	Op Para.	-	RPX, Rad, Wind S&D	Multiplex	-	Transmitters	1	10	-	3.6	Volt	-
11	LHR	186 $\frac{1}{4}$	Side NA	Dyadic	Long.	H. Bend	1	11	-	8214	PSI	2
12	SFP	265	P Side 32' ATT	Shear	Vert.	Shear	1	12	-	5000	PSI	4
13	SFS	265	S Side 32' ATT	Shear	Vert.	Shear	1	13	-	5000	PSI	4
14 (1)	LVB	186	S Tunnel Top	Dyadic	Long.	N. Stress	2	1	A	8240	PSI	5
15	LSIS	186	S Side N.A.	Dyadic	Long.	N. Stress	2	2	A	8240	PSI	5
16	LSNS	186	S Side Bottom	Dyadic	Long.	N. Stress	2	3	A	8240	PSI	5
17	LSBS	186	P Tunnel Top	Dyadic	Long.	N. Stress	2	4	A	8240	PSI	5
18	LSTP	186	P Side NA	Dyadic	Long.	N. Stress	2	5	A	8240	PSI	5
19	LSXP	186	P Side Bottom	Dyadic	Long.	N. Stress	2	6	A	8240	PSI	5
20	LSTP	186	P Side 26' ATT	Dyadic	Long.	N. Stress	2	7	A	8240	PSI	5
21	SAP	87	P Side 26' ATT	Shear	Vert.	Shear	2	8	A	5000	PSI	4
22	SAS	87	S Side 26' ATT	Shear	Vert.	Shear	2	9	A	5000	PSI	4

TABLE I (Continued)

SENSOR LIST
72/73 Season and Calibration

Sensor No.	Sensor Nom.	Frame	Location (2) Position	Config.	Orient	Sensitive to	Recorder	Channel	Mode	Full Cal	Units	Circuit No.
23	FDW	307	Level 04 CL	Mass	Vert.	V. Accel.	2	10	A	+1 (4)	B	-
24	FDH	307	Level 04 CL	Mass	Trans.	T. Accel.	2	11	A	+1	B	-
25	ADHL	139	Level 05 1" P	Mass	Long.	L. Accel.	2	10 (a)	A	+1	B	-
26	ADHF	130	Level 05 1" P	Mass	Trans.	T. Accel.	2	11 (a)	A	+1	B	-
27	BCT	186 1/4	S Tunnel Top	Shear	Long.	Shear	2	12	A	5000	PSI	4
28	BCH	186 1/4	S Tunnel Bot	Shear	Long.	Shear	2	13	A	5000	PSI	4
29 (1)	L13						2	1	B			
30	AR-1A	143	Port Side Girder Near Deck Cutout	Single	Long.	N. Strain	2	2	B	334.6	µ"/"	6
31	AR-1B	143		Single	Diag.	N. Strain	2	3	B	334.6	µ"/"	6
32	AR-1C	143		Single	Trans.	N. Strain	2	4	B	334.6	µ"/"	6
33	AR-2A	143	Stbd Side Girder Near Deck Cutout	Single	Long.	N. Strain	2	5	B	334.6	µ"/"	6
34	AR-2B	143		Single	Diag.	N. Strain	2	6	B	334.6	µ"/"	6
35	AR-2C	143		Single	Trans.	N. Strain	2	7	B	334.6	µ"/"	6
36	AR-3A	143	Stbd Tunnel In Board	Single	Long.	N. Strain	2	8	B	334.6	µ"/"	6
37	AR-3B	143		Single	Diag.	N. Strain	2	9	B	334.6	µ"/"	6
38	AR-3C	143		Single	Trans.	N. Strain	2	10	B	334.6	µ"/"	6
39	AR-4A	143	Stbd Tunnel Out Board	Single	Long.	N. Strain	2	11	B	334.6	µ"/"	6
40	AR-4B	143		Single	Diag.	N. Strain	2	12	B	334.6	µ"/"	6
41	AR-4C	143		Single	Trans.	N. Strain	2	13	B	334.6	µ"/"	6

3.

TABLE I (Continued)

SENSOR LIST
72/73 Season and Calibration

Sensor No.	Sensor Nom.	Location(2)		Config.	Orient	Sensitive to	Recorder	Channel	Mode	Full Cal	Units	Circuit No.
		Frame	Position									
42 (1)	LVB						2	1	C			6
43	R1A	291	Port Side Gird	Single	Long.	N. Strain	2	2-13	C	334.6	μ"/"	6
44	R1B	291	Near Deck Cutout	Single	Diag.	N. Strain	2	VIA	C	334.6	μ"/"	6
45	R1C	291	Under Deck	Single	Trans.	N. Strain	2	RSB	C	334.6	μ"/"	6
46	R2A	291	Stbd Side Gird	Single	Long.	N. Strain	2	2-13	C	334.6	μ"/"	6
47	R2B	291	Near Deck Cutout	Single	Diag.	N. Strain	2	VIA	C	334.6	μ"/"	6
48	R3C	291	Under Deck	Single	Trans.	N. Strain	2	RSB	C	334.6	μ"/"	6
49	R3A	291	Stbd Tunnel	Single	Long.	N. Strain	2	2-13	C	334.6	μ"/"	6
50	R3B	291	In Board	Single	Diag.	N. Strain	2	VIA	C	334.6	μ"/"	6
51	R3C	291	Under Deck	Single	Trans.	N. Strain	2	RSB	C	334.6	μ"/"	6
52	R4A	291	Stbd Tunnel	Single	Long.	N. Strain	2	2-13	C	334.6	μ"/"	6
53	R4B	291	Out Board	Single	Diag.	N. Strain	2	VIA	C	334.6	μ"/"	6
54	R4C	291	Under Deck	Single	Trans.	N. Strain	2	RSB	C	334.6	μ"/"	6
55	R5A	258	Stbd Side Gird	Single	Long.	N. Strain	2	2-13	C	334.6	μ"/"	6
56	R5B	258	In Corn. Hat 2	Single	Diag.	N. Strain	2	VIA	C	334.6	μ"/"	6
57	R5C	258	Under Deck	Single	Trans.	N. Strain	2	RSB	C	334.6	μ"/"	6
58	R6A	258	Stbd Side Gird	Single	Long.	N. Strain	2	2-13	C	334.6	μ"/"	6
59	R6B	258	Out Corn. Hat 2	Single	Diag.	N. Strain	2	VIA	C	334.6	μ"/"	6
60	R6C	258	Under Deck	Single	Trans.	N. Strain	2	RSB	C	334.6	μ"/"	6
61	R7A	258	Stbd Side Gird	Single	Long.	N. Strain	2	2-13	C	334.6	μ"/"	6
62	R7B	258	Near Deck Cutout	Single	Diag.	N. Strain	2	VIA	C	334.6	μ"/"	6
63	R7C	258	Under Deck	Single	Trans.	N. Strain	2	RSB	C	334.6	μ"/"	6
64	R3A	258	Stbd Tunnel	Single	Long.	N. Strain	2	2-13	C	334.6	μ"/"	6
65	R3B	258	In Board	Single	Diag.	N. Strain	2	VIA	C	334.6	μ"/"	6
66	R3C	258	Under Deck	Single	Trans.	N. Strain	2	RSB	C	334.6	μ"/"	6

TABLE I (Continued)

SENSOR LIST
72/73 Season and Calibration

Sensor No.	Sensor Nom.	Location (2)		Config.	Orient	Sensitive to	Recorder	Channel	Mode	Full Cal	Units	Circuit No.
		Frame	Position									
67	R9A	258	Stbd Tunnel	Single	Long.	N. Strain	2	2-13	C	334.6	μ "/"	6
68	R9B	258	Out Board	Single	Diag.	N. Strain	2	VIA	C	334.6	μ "/"	6
69	R9C	258	Under Deck	Single	Trans.	N. Strain	2	RSB	C	334.6	μ "/"	6
70	R10A	226	Stbd Side Gird	Single	Long.	N. Strain	2	2-13	C	334.6	μ "/"	6
71	R10B	226	In Corn. Hat 4	Single	Diag.	N. Strain	2	VIA	C	334.6	μ "/"	6
72	R10C	226	Under Deck	Single	Trans.	N. Strain	2	RSB	C	334.6	μ "/"	6
73	R11A	226	Stbd Side Gird	Single	Long.	N. Strain	2	2-13	C	334.6	μ "/"	6
74	R11B	226	Out Corn Hat 4	Single	Diag.	N. Strain	2	VIA	C	334.6	μ "/"	6
75	R11C	226	Underdeck	Single	Trans.	N. Strain	2	RSB	C	334.6	μ "/"	6
76	R12A	226	Stbd Side Gird	Single	Long.	N. Strain	2	2-13	C	334.6	μ "/"	6
77	R12B	226	Near Deck Cutout	Single	Diag.	N. Strain	2	VIA	C	334.6	μ "/"	6
78	R12C	226	Underdeck	Single	Trans.	N. Strain	2	RSB	C	334.6	μ "/"	6
79	R13A	226	Stbd Tunnel	Single	Long.	N. Strain	2	2-13	C	334.6	μ "/"	6
80	R13B	226	In Board	Single	Diag.	N. Strain	2	VIA	C	334.6	μ "/"	6
81	R13C	226	Under Deck	Single	Trans.	N. Strain	2	RSB	C	334.6	μ "/"	6
82	R14A	226	Stbd Tunnel	Single	Long.	N. Strain	2	2-13	C	334.6	μ "/"	6
83	R14B	226	Out Board	Single	Diag.	N. Strain	2	VIA	C	334.6	μ "/"	6
84	R14C	226	Under Deck	Single	Trans.	N. Strain	2	RSB	C	334.6	μ "/"	6
85 (1)	LVB						2	1	D			
86	TCFS1	244	Fwd Top	Single	Trans.	N. Stress	2	2	D	10038	PSI	6

TABLE I (Continued)

SENSOR LIST
72/73 Season and Calibration

Sensor No.	Sensor Nom.	Location (2)		Config.	Orient	Sensitive to	Recorder	Channel	Mode	Full Cal	Units	Circuit No.
		Frame	Position									
87	HLSS1	289	S Side 1' BT	Single	Long.	N. Stress	2	2 (a)	D	10038	PSI	6
88	TGFS2	244	Fwd Bot.	Single	Trans.	N. Stress	2	3	D	10038	PSI	6
89	HLSS3	289	S Side 1' ATT	Single	Long.	N. Stress	2	3 (a)	D	10038	PSI	6
90	TGFS3	242	Aft Bot	Single	Trans.	N. Stress	2	4	D	10038	PSI	6
91	HLSP1	289	P Side 1' BT	Single	Long.	N. Stress	2	4 (a)	D	10038	PSI	6
92	TGFS4	242	Aft Top	Single	Trans.	N. Stress	2	5	D	10038	PSI	6
93	HLSPB	289	P Side 1' ATT	Single	Long.	N. Stress	2	5 (a)	D	10038	PSI	6
94	TGMS1	196	Fwd Gird. Top	Single	Trans.	N. Stress	2	6	D	10038	PSI	6
95	TGMS2	196	Fwd Gird Bot.	Single	Trans.	N. Stress	2	7	D	10038	PSI	6
96	TGMS3	194	Aft Gird Bot.	Single	Trans.	N. Stress	2	8	D	10038	PSI	6
97	TGMS4	194	Aft Gird Top	Single	Trans.	N. Stress	2	9	D	10038	PSI	6
98	TGMS1X	194	Fwd Gird Mid	Single	Trans.	N. Stress	2	6 (a)	D	10038	PSI	6
99	TGMS2X	195	Bot Gird Mid	Single	Trans.	N. Stress	2	7 (a)	D	10038	PSI	6
100	TGMS3X	194	Aft Gird Mid	Single	Trans.	N. Stress	2	8 (a)	D	10038	PSI	6
101	TGMS4X	195	Top Gird Mid	Single	Trans.	N. Stress	2	9 (a)	D	10038	PSI	6
102	TGSS1X	196	Fwd Gir Q Top	Shear	Trans.	Shear	2	6 (a)	D	5000	PSI	4
103	TGSS2X	196	Fwd Gir Q Bot	Shear	Trans.	Shear	2	7 (a)	D	5000	PSI	4
104	TGSS3X	194	Aft Gir Q Bot	Shear	Trans.	Shear	2	8 (a)	D	5000	PSI	4
105	TGSS4X	194	Aft Gir Q Top	Shear	Trans.	Shear	2	9 (a)	D	5000	PSI	4
106	TGAS1	80	Fwd Top	Single	Trans.	N. Stress	2	10	D	10038	PSI	6
107	TGAS2	80	Fwd Bot	Single	Trans.	N. Stress	2	11	D	10038	PSI	6
108	TGAS3	78	Aft Bot	Single	Trans.	N. Stress	2	12	D	10038	PSI	6
109	TGAS4	78	Aft Top	Single	Trans.	N. Stress	2	13	D	10038	PSI	6

TABLE II

SENSOR AND SIGNAL NOMENCLATURE

ADHL	After Deck House Longitudinal (Acceleration)
ADHT	After Deck House Transverse (Acceleration)
AR ₁₋₄ (Z)	Aft Rosettes, (Z) denotes gage element: A is longitudinal orientation B is diagonal (45°) orientation C is transverse (athwart) to longitudinal
BGSB	Box Girder Shear Bottom
BGST	Box Girder Shear Top
FAV	Forward Acceleration Vertical (Hull)
FAT	Forward Acceleration Transverse (Hull)
FDHT	Forward Deck House Transverse (Acceleration)
FDHV	Forward Deck House Vertical (Acceleration)
HLSPB	Hull Longitudinal Strain Port Bottom
HLSPB	Hull Longitudinal Strain Port Top
HLSSB	Hull Longitudinal Strain Starboard Bottom
HLSSB	Hull Longitudinal Strain Starboard Top
LHB	Longitudinal Horizontal Bending (combination of LHBP and LHBS)
LHBP	Longitudinal Horizontal Bending Port (Stress)
LHBS	Longitudinal Horizontal Bending Starboard (Stress)
LSBP	Longitudinal Stress Bottom Port
LSBS	Longitudinal Stress Bottom Starboard
LSMP	Longitudinal Stress Mid Port
LSMS	Longitudinal Stress Mid Starboard
LSTP	Longitudinal Stress Top Port
LSTS	Longitudinal Stress Top Starboard

TABLE II (Continued)

SENSOR AND SIGNAL NOMENCLATURE

LVB	Longitudinal Vertical Bending (combination of LVBP and LVBS)
LVBP	Longitudinal Vertical Bending Port (Stress)
LVBS	Longitudinal Vertical Bending Starboard (Stress)
MAT	Midship Acceleration Transverse (Hull)
MAV	Midship Acceleration Vertical (Hull)
R ₁₋₄ (Z)	Rosettes (Forward), (Z) denotes gage element: A is longitudinal orientation B is diagonal (45°) orientation C is transverse (athwart) to longitudinal
SAP	Shear Aft Port
SAS	Shear Aft Starboard
SFP	Shear Forward Port
SFS	Shear Forward Starboard
TGAS ₁₋₄	Transverse Girder Aft Starboard (Strain)
TGFS ₁₋₄	Transverse Girder Forward Starboard (Strain)
TGMS ₁₋₄	Transverse Girder Midship Starboard (Strain)
TGMS _{1X-4X}	Transverse Girder Midship Starboard (Strain, midpoints)
TGSS _{1X-4X}	Transverse Girder Shear Starboard (Midships, vertical quarterpoints)
TSM	Torsional Shear Midship (combination of TSMP and TSMS)
TSMP	Torsional Shear Midship Port
TSMS	Torsional Shear Midship Starboard

TABLE III

SIGNAL DESCRIPTION AND RATIONALE

RECORDER NO. 1

Channel(s)

- 1 Vertical Bending: Longitudinal stress gages, P&S, under deck, near midship (Frame 186 1/4), in box girder wired to eliminate longitudinal horizontal bending; primary reference stress; provides data comparable to SSC Project SR-153 and ABS 5-Vessel program. This signal serves as a common reference with each group of gages.
- 2 Midship Torsional Shear: Shear rosettes amidship (Frame 186 1/4) P&S, on sideshell at neutral axis wired into single bridge to eliminate shear associated with vertical bending. Will show shear associated with torsion and horizontal bending. Primary value is in comparison with similar SS BOSTON data.
- 3 Wave Height: Reserved for output of a wave height sensor.
- 4,5 Roll and Pitch: Pendulums, roll and pitch angle transducers located close to vertical and longitudinal vessel CG (Frame 178). Rigid body motions. Similar to BOSTON data; useful in container load evaluation.
- 6,7 Hull Accelerations: Vertical and transverse accelerometers located at vessel CG (Frame 178), similar to array used on BOSTON. Vertical unit required for heave acceleration.
- 8,9 Hull Accelerations: Vertical and transverse accelerometers located forward (Frame 290). Rigid body as well as whipping motions. Useful for comparison with WOLVERINE STATE and BOSTON data, and probably indicative of most severe accelerations on vessel.
- 10 Multiplexed Ship Parameters: RPM, rudder angle, wind speed and direction.
- 11 Horizontal Bending: Longitudinal stress gages, P&S, near midship (Frame 186 1/4), at neutral axis; wired to provide a longitudinal horizontal bending signal.
- 12,13 Shear-Forward: Shear rosettes near forward quarter point (Frame 265-266), P&S, on sideshell, at neutral axis. P&S recorded separately since shear associated with vertical bending may be of major interest here; signals can be recombined on playback to produce shear component associated with vertical bending or torsion.

TABLE III (Continued)

RECORDER NO. 2, MODE A

Channel(s)

- 1 Vertical Bending: Reference signal
- 2,3,4,5,6,7 Longitudinal Stress Gages: Six stress gages at deck, neutral axis, and bottom (lower sidshell), P&S, amidship (Frame 186 1/4). Recorded separately, but data can be combined to provide signals proportional to longitudinal vertical bending, longitudinal horizontal bending, and warping longitudinal stresses. Neutral axis gages added to simplify direct evaluation of transverse stresses and subsequent separation of vertical and warping stresses. First time this array has been used.
- 8,9 Shear-Aft: Shear rosettes near after quarter point (Frame 87-88) P&S, on sidshell, 18.2' at above neutral axis P&S recorded separately. Torsional shear was initial concern, but present interest is in shear associated with vertical bending as well. Separate recording permits recombination of signals to produce shear component associated with vertical bending or torsion.
- 10,11 Deckhouse Accelerations: Vertical and transverse accelerometers mounted high near centerline in the forward house, and transverse and longitudinal accelerometers in the after house. Any two of the four signals may be recorded at one time. Primary interest is in possible springing or higher frequency vibratory effects.
- 12,13 Box Girder Shear: Shear rosettes located on overhead and deck of starboard box girder. Each recorded independently; a torsional shear in the box girder can be reduced from these signals.

RECORDER NO. 2, MODE B

Channel(s)

- 1 Vertical Bending: Reference signal.
- 2 thru 13 After Hatch Corner: Four, three-arm strain gage rosettes will be placed in an athwartship array under the deck between Frame 143-144, just forward of the after house. Of interest here is the transfer of longitudinal stress (from all sources--torsion, vertical bending, etc.) from the box beam ligament structure in way of the holds to the relatively complete and rigid hull at the house. The gross hatch corner stress concentration will also be

TABLE III (Continued)

Channel(s)

evaluated port and starboard. Original suggestion of ABS, but this and following locations shown to be of concern in California model work and British, German, and Japanese model and full-scale tests.

RECORDER NO. 2, MODE C

This gage group is the same as Gage Group 3, except that the rosettes are located at one of the following positions:

- 5 Rosettes at Frame 226-227 (hatch transition)
- 5 Rosettes at Frame 258-260 (hatch transition) and
- 4 Rosettes at Frame 290-291 (aft of Fwd Deckhouse)

Since Gage Group 4 consists of 14 rosettes with 3 elements per rosette for a total of 42 separate signals; some means was required to allow for a selection of inputs into the 12 recorder channels available.

A patching unit designated the "Rosette Selection Box" (RSB) has been installed in the starboard box girder at approximately Frame 272. This unit takes the 14 rosette signals as inputs and by means of patching cable allows the operator to select any 4 rosettes as input to the recorder. The only restriction is that all elements, i.e., the A, B, and C arms of any rosette must be recorded together.

RECORDER NO. 2, MODE D

Channel(s)

- 1 Vertical Bending: Reference signal.
- 2,3,4,5 Gages in Transverse Deck Girder: Four single gages mounted at the corners of a transverse deck girder, Frames 242-244. Double-S bending in girder used as measure of torsional hull deflection at that frame. Similar to BOSTON arrays. Or, by PSU selection, four single strain gages around the hull section at Frame 240 (2 top, 2 bottom) to measure strain distribution at this location.
- 6,7,8,9 Gages in Transverse Deck Girder: Same as above at Frames 194-196.

In addition to the four corner gages, four additional single element gages have been placed at the midpoint of each dimension of the girder. Four 2-element shear gages have been installed at the quarter points of the two side walls.

TABLE III (Concluded)

In a manner similar to the rosette selection technique it was again necessary to select four of twelve signals available for recording. This time a similar Girder Selection Box (GSB) was installed in the starboard box girder at Frame 194.

The selection was limited to three possible combinations due to wiring and bridge requirements.

The three possible patches are:

- (1) 4 corner gages
- (2) 4 midpoint gages
- (3) 4 shear gages (quarter points)

It is possible to mix signals but additional changes are required at the signal conditioning equipment.

10,11,12,13 Gages in Transverse Deck Girder: Same as above at Frame 78-80.

TABLE IV
ENVIRONMENTAL CONDITION AT CALIBRATION

Cond.	Time	Air, Dry		Temperatures, °F		Stbd Tunnel*		Location of Sun, degrees Azimuth**	Wind		
		49.5	43	Air Wet	Water	Port Tunnel*	Elevation		Speed, mph	Direction	
1	9 Apr '73 0900	49.5	43	43	43	51	52	45 (Overcast)	50 Stbd	15	60° Port
3	1300	58	50.5	43	43	49	64	60 (Clear)	100 Stbd	20	60° Port
4	1725	49	44	43	43	49	63	30 (Clear)	Aft	10	110° Port
5	2130	38	36	43	43	45	52	-	-	8	90° Port
6	10 Apr '73 0105	36.5	35	43	43	43	46	-	-	12	60° Port
7	0830	40	-	42	40	40	46	-	-	10	90° Port

Notes:

* Measured on hull plating backside

** Relative to ship




TABLE V
OBSERVED DRAFTS

Condition	PORT			STBD		
	Fwd	Mid	Aft	Fwd	Mid	Aft
1	30' 11"	31' 0"	31' 1"	-	-	-
3	28' 11"	-	29' 11 1/2"	28' 11"	27' 11"	29' 7 1/2"
4	27' 2"	-	28' 9"	27' 2"	26' 9"	28' 9"
5	25' 5"	-	27' 1"	25' 5"	25' 1"	27' 0"
6	23' 0"	-	26' 11"	23' 2"	24' 5"	26' 10"

MATCH LIST BATCH NO 01 S E A - L A H D S L R V I C E I N G PAGE NO 502
 VESSEL SL PCLEAR VOYAGE 012# PARTER
 PORT DEPARTURE ORV DESTINATION ROT DATE 04/08/73
 FINAL PLAN

TABLE VI
 CALIBRATION UNLOADING PLAN

POST	CENTER LINE	STBD	DIFF DIR	TOTAL WT
101.7	.0	113.1	11.4 STBD	
57.6	44.1	58.6	54.5	21.5
0409	10.5	0209	22.1 0109 20.0	18.0
SLS 38479		SLS 63887	950113	
BRV-FEL		BRV-FEL	ELZ-ROTTN	60.2
0503	23.5	0503	23.4	
SLS 95731		SLS 95626	ELZ-ROTTN	
ELZ-ROTTN		ELZ-ROTTN		
0608	23.6	0208	22.0 0109 20.6	136.5
SLS 95932		SLS 60429	950112	
ELZ-ROTTN		BRV-FEL	ELZ-ROTTN	
57.6	44.1	58.6	54.5	21.5
POST	CENTER LINE	STBD	DIFF DIR	TOTAL WT
101.7	.0	113.1	11.4 STBD	
0607	9.2 3407 8.5	0107	13.2	31.2
SLS 7221	SLS 70739	301016		
ELZ-ROTTN	ELZ-ROTTN	ELZ-ROTTN		
0609	10.2 1406 19.9 0206 11.5	0106	13.6 0306 21.6	76.8
SLS 95959	SLS 70267	SLS 37498	501703	
ELZ-ROTTN	ELZ-ROTTN	BAL-ROTTN	ELZ-ROTTN	
0403	18.5 0205 14.5	0105	15.2 0305 21.7	69.7
ELZ-FEL	BAL-ROTTN	301733	301209	
ELZ-FEL	BAL-ROTTN	ELZ-ROTTN	ELZ-ROTTN	
0404	20.3 0204 16.2	0104	15.0 0304 24.5	76.8
SLS 69781	SLS 67701	SLS 63391	301473	
ELZ-FEL	BAL-ROTTN	BAL-FEL	ELZ-ROTTN	
0201	18.3 0103 16.1	0103	16.1	36.4
SLS 44230	SLS 35943	ELZ-ROTTN	ELZ-FEL	
ELZ-ROTTN				
0202	19.8 0102 19.4	0102	19.4	39.2
SLS 55291	SLS 50659	BAL-FEL	ELZ-ROTTN	
BAL-FEL				
0201	21.9 0101 20.8	0101	20.8	42.7
SLS 39120	SLS 69073	BAL-LHA	ELZ-ROTTN	
BAL-LHA				
19.7	67.2	102.2	116.1	373.0
POST	CENTER LINE	STBD	DIFF DIR	TOTAL WT

Removed for Cond. 3

Removed for Cond. 6

HATCH LIST HATCH NO 02 S E A - L A N D S E R V I C E I N C P A S T E R P A G E N O 003
 VESSEL SL RCLEAN VOYAGE 0124 H P A S T E R 04/02/73
 PORT DEPARTURE BHV DESTINATION ROT

TABLE VI (Cont'd)

30.4	89.1	89.8	133.5	135.2	90.0	49.1	25.3	25.7	61.4	23.3	25.3	201.5
PORT	PORT	PORT	CENTER LINE	CENTER LINE	STBD	DIFF DIR	STBD	DIFF DIR	STBD	DIFF DIR	STBD	TOTAL WT
272.1	272.1	272.1	.0	.0	274.3	2.2	25.3	2.2	25.3	2.2	25.3	747.9
0809 22.4 SLS 69779 GRA-ROT	0209 17.1 0109 17.7 0309 20.1 SLS 69621 SLS 73986 SLS 95598 GRA-ROT GRA-ROT ELZ-ROTH	0209 20.8 SLS 95388 JAX-FELIN	0208 20.8 0108 8.0 0308 20.8 SLS 95910 SLS 52047 SLS 92593 JAX-FELT3 ELZ-ROT G JAX-FELTR	0207 16.0 0107 17.7 SLS 50849 SLS 57754 NRF-VAL CHS-VAL	0206 12.1 0206 18.5 SLS 61586 SLS 65575 BAL-LHA NRF-NAP	0205 17.3 0205 18.5 SLS 74241 SLS 64950 BAL-FEL NRF-NAP	0204 17.5 0204 18.7 SLS 50657 SLS 66090 JAX-CDZ NRF-NAP	0203 20.1 0103 19.9 0303 21.7 SLS 37034 SLS 46057 BAL-ROT BAL-NRS ELZ-VAL ELZ-ROT	0202 22.1 0202 20.8 SLS 40915 SLS 37217 ELZ-ROT JAX-CDZ	0201 20.9 0101 20.8 SLS 17353 SLS 46940 BAL-FEL JAX-CDZ	0709 17.5 SLS 37782 BHV-ROT	0708 7.8 SLS 51293 BAL-ROT 5
												94.8
												106.7
												201.5
												TOTAL WT
												747.9
												62.9
												97.6
												103.4
												72.0
												32.5
												86.4
												41.7
												546.4
												TOTAL WT
												747.9

VI-2

TABLE VI (Cont'd)

PORT	137.7	CENTER LINE	40.6	42.2	38.1	22.5	21.0	19.9	39.4	TOTAL WT
PORT	378.0	CENTER LINE	112.0	103.2	81.9	43.5	36.9	28.0	568.3	TOTAL WT
1009 17.7	0409 21.5 0209 17.7 0109 17.7	20.4 0308 22.5 0508 21.0 0708 19.9 0908 21.7	200249 SLS 26371 SLS 26254 SLS 29871	200152 851000	ELZ-PTNX ELZ-FELX LBC-ROTX ELZ-FELX	200249 SLS 26371 SLS 26254 SLS 29871	200152 851000	200249 SLS 26371 SLS 26254 SLS 29871	200152 851000	92.3
SLS 22036	SLS 22648 SLS 28592 SLS 28931	ELZ-FELX BOS-PTNX	ELZ-FELX BOS-PTNX	ELZ-FELX BOS-PTNX	ELZ-FELX BOS-PTNX	ELZ-FELX BOS-PTNX	ELZ-FELX BOS-PTNX	ELZ-FELX BOS-PTNX	ELZ-FELX BOS-PTNX	92.3
BOS-FELX	ELZ-FELX BOS-PTNX	BOS-PTNX	BOS-PTNX	BOS-PTNX	BOS-PTNX	BOS-PTNX	BOS-PTNX	BOS-PTNX	BOS-PTNX	92.3
1008 17.7	0608 19.5 0406 19.1 0208 24.5 0108 20.4 0308 22.5 0508 21.0 0708 19.9 0908 21.7	200249 SLS 26371 SLS 26254 SLS 29871	200152 851000	200249 SLS 26371 SLS 26254 SLS 29871	200152 851000	200249 SLS 26371 SLS 26254 SLS 29871	200152 851000	200249 SLS 26371 SLS 26254 SLS 29871	200152 851000	278.6
SLS 23920	SLS 24062	LBC-PTNX ELZ-ROTX ELZ-ELIX ELZ-FELX	LBC-PTNX ELZ-ROTX ELZ-ELIX ELZ-FELX	LBC-PTNX ELZ-ROTX ELZ-ELIX ELZ-FELX	LBC-PTNX ELZ-ROTX ELZ-ELIX ELZ-FELX	LBC-PTNX ELZ-ROTX ELZ-ELIX ELZ-FELX	LBC-PTNX ELZ-ROTX ELZ-ELIX ELZ-FELX	LBC-PTNX ELZ-ROTX ELZ-ELIX ELZ-FELX	LBC-PTNX ELZ-ROTX ELZ-ELIX ELZ-FELX	278.6
BOS-PTNX	ELZ-PTNX ELZ-FELX	ELZ-FELX	ELZ-FELX	ELZ-FELX	ELZ-FELX	ELZ-FELX	ELZ-FELX	ELZ-FELX	ELZ-FELX	278.6
35.4	19.5	40.6	42.2	38.1	22.5	21.0	19.9	39.4	278.6	TOTAL WT
PORT	137.7	CENTER LINE	40.6	42.2	38.1	22.5	21.0	19.9	39.4	TOTAL WT
PORT	378.0	CENTER LINE	112.0	103.2	81.9	43.5	36.9	28.0	568.3	TOTAL WT
PORT	378.0	CENTER LINE	112.0	103.2	81.9	43.5	36.9	28.0	568.3	TOTAL WT
PORT	378.0	CENTER LINE	112.0	103.2	81.9	43.5	36.9	28.0	568.3	TOTAL WT

Removed for Cond. 6

0607 13.9 0407 13.9 0207 12.4	0107 2.5	SLS 48776 SLS 41886 SLS 45236	SLS 64517	ELZ-LEG ELZ-LEG ELZ-LEG	#EMPTY# E	42.7			
0606 16.4 0406 14.6 0206 12.7	0106 12.4	SLS 62279 SLS 65932 SLS 64265	SLS 55075	ELZ-LEG ELZ-LEG ELZ-LEG	0706 4.7	60.3			
SLS 62279 SLS 65932 SLS 64265	SLS 55075	ELZ-LEG ELZ-LEG ELZ-LEG	ELZ-LEG	00S-PTN	SLS 54198	74.8			
0305 9.5 06.5 17.1 0405 17.1 0205 12.9	0105 12.5	SLS 69016 SLS 72487 SLS 33761 SLS 63811	SLS 69118	ELZ-VAL ELZ-VAL BOS-COA ELZ-LEG	0705 5.7	90.1			
SLS 69016 SLS 72487 SLS 33761 SLS 63811	SLS 69118	ELZ-VAL ELZ-VAL BOS-COA ELZ-LEG	ELZ-LEG	00S-PTN	SLS 39265	106.9			
0604 13.7 0604 16.8 0404 15.2 0204 13.5	0104 12.8	SLS 54026 SLS 6102 SLS 70711 SLS 58045	SLS 53241	ELZ-LEG ELZ-RO1 ELZ-LEG ELZ-LEG	0504 7.5 0704 8.6	111.2			
SLS 54026 SLS 6102 SLS 70711 SLS 58045	SLS 53241	ELZ-LEG ELZ-RO1 ELZ-LEG ELZ-LEG	ELZ-LEG	0504 7.5 0704 8.6	SLS 47586 SLS 65180	81.8			
0503 22.3 0603 23.2 0403 17.6 0203 13.8	0103 13.5	SLS 301729 SLS 29177 SLS 64490 SLS 55197	SLS 67538	ELZ-FEL ELZ-FEL ELZ-GOA ELZ-LEG	0503 8.8 0703 9.0	106.9			
SLS 301729 SLS 29177 SLS 64490 SLS 55197	SLS 67538	ELZ-FEL ELZ-FEL ELZ-GOA ELZ-LEG	ELZ-LEG	0503 8.8 0703 9.0	SLS 34555 SLS 52676	106.9			
0602 23.5 0402 17.7 0202 15.2	0102 19.7 0302 20.4	SLS 22589 SLS 70787 SLS 61931	SLS 17033	ELZ-FEL ELZ-FEL ELZ-FEL ELZ-LEG	0502 20.6	111.2			
SLS 22589 SLS 70787 SLS 61931	SLS 17033	ELZ-FEL ELZ-FEL ELZ-FEL ELZ-LEG	ELZ-LEG	0502 20.6	950099	111.2			
0401 21.5 0201 22.7 8101 14.5 0301 23.1	8101 14.5 0301 23.1	SLS 71720 SLS 61192	SLS 59062	BOS-CDZ BOS-CDZ ELZ-LEG ELZ-RO1	ELZ-ROTTW ELZ-ROTTN	81.8			
SLS 71720 SLS 61192	SLS 59062	BOS-CDZ BOS-CDZ ELZ-LEG ELZ-RO1	ELZ-RO1	ELZ-ROTTW ELZ-ROTTN	ELZ-ROTTW ELZ-ROTTN	81.8			
45.2	112.0	103.2	81.9	43.5	36.9	28.0	568.3	TOTAL WT	946.9

HATCH LIST HATCH NO 05
 VESSEL SL MCLEAN
 PORT DEPARTURE BIW
 FINAL PLAN

SEA - LAND SERVICE INC -

Voyage 012W
 DESTINATION ROT

MASTER
 DATE 04/02/73

PAGE NO 006

TABLE VI - (Cont'd)

1010	4.3	0810	4.8	0610	6.8	0410	5.1	0210	4.9	0110	4.4	0310	9.1	0510	9.1	0710	5.0	0910	5.1		
SLS	62651	SLS	52744	SLS	69659	SLS	73960		302069	SLS	71077	SLS	60023	SLS	52759	SLS	41615	SLS	62873		
CHS-ROT	ELZ-ROT	G	ELZ-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	NRF-ROT	CHS-ROT	CHS-ROT							
																					58.6
1009	10.4	0809	10.7	0609	21.5	0409	10.8	0209	12.2	0109	12.3	0309	12.1	0509	8.6	0709	21.3	0909	10.7		
SLS	48726	SLS	63320	SLS	29184	SLS	26832	SLS	29765		200483		200596		200452	SLS	20874	SLS	39307		
NRF-ROT	ELZ-ROT	ELZ-LHAX	ELZ-ROT	G	NRF-ROT	NRF-ROT	NRF-ROT	NRF-ROT	NRF-ROT	NRF-ROT	NRF-ROT	NRF-ROT	NRF-ROT	NRF-ROT	NRF-ROT	ELZ-LHAX	ELZ-ROT	G			
																					130.6
1008	16.0	0608	16.2	0408	16.2	0208	16.5	0108	13.9	0308	12.5	0508	15.1	0708	14.1	0908	15.3	0908	13.2	Removed	
	200550		260601		200602	SLS	23141		200463	SLS	23035		200082	SLS	26383		200490		200619	for Cond.	
NRF-ROTX	NRF-ROTX	NRF-ROTX	ELZ-ROTX	NRF-ROTX	ELZ-ROTX	NRF-ROTX	ELZ-ROTX	CHS-ROTX	NRF-ROTX	NRF-ROTX	NRF-ROTX	NRF-ROTX	NRF-ROTX	NRF-ROTX	NRF-ROTX	NRF-ROTX	NRF-ROTX			4	
																					149.0
																					338.2
																					30.7
																					31.7
																					44.5
																					32.4
																					31.0
																					29.2
																					36.3
																					31.8
																					41.6
																					29.0
																					TOTAL WT
																					170.3
																					CENTER LINE
																					.0
																					STBD
																					167.9
																					DIFF DIR
																					2.4
																					PORT
																					Removed for Cond. 5
1007	12.5			0607	14.5	0407	14.8	0207	17.6	0107	17.5	0307	14.6	0507	14.4					0907	13.2
SLS	17127			SLS	39353	SLS	32234	SLS	39216	SLS	34582	SLS	30760	SLS	33696					SLS	64801
ELZ-ROT	G			JAX-ROT	JAX-ROT	NRF-ROT	NRF-ROT	NRF-ROT	NRF-ROT	NRF-ROT	NRF-ROT	CHS-ROT								ELZ-ROT	G
																					119.1
1006	17.9	0806	13.5	0606	18.1	0406	19.6	0206	19.6	0106	19.6	0306	19.6	0506	19.6	0706	14.0	0906	17.9		
SLS	59640	SLS	45477	SLS	59595	SLS	44604	SLS	47642	SLS	45206	SLS	45735	SLS	40088	SLS	57398	SLS	45652		
NRF-ROT	ELZ-ROT	G	NRF-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	ELZ-ROT	G	NRF-ROT			
																					179.4
1005	20.0	0805	18.1	0605	20.3	0405	20.8	0205	21.1	0105	20.8	0305	22.6	0505	20.3	0705	18.0	0905	19.6		
SLS	54477	SLS	73215	SLS	43926	SLS	39388	SLS	46035	SLS	47949	SLS	53364	SLS	69533	SLS	61267	SLS	42781		
ELZ-ROT	CHS-ROT	ELZ-ROT	NRF-ROT	NRF-ROT	NRF-ROT	NRF-ROT	NRF-ROT	NRF-ROT	NRF-ROT	NRF-ROT	NRF-ROT	NRF-ROT	NRF-ROT	NRF-ROT	CHS-ROT	CHS-ROT	CHS-ROT				
																					201.6
0804	20.2	0504	21.7	0404	22.6	0204	22.3	0104	22.1	0304	20.8	0504	21.7	0704	20.1						
SLS	51308	SLS	60287	SLS	60819	SLS	34585	SLS	34442	SLS	50109	SLS	38075	SLS	48254						
ELZ-ROT	JAX-ROT	JAX-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	JAX-ROT	NRF-ROT	JAX-ROT	BAL-ROT										
																					171.5
0103	21.7	0603	22.6	0403	22.0	0203	22.6	0103	22.7	0303	21.8	0503	22.5	0703	21.7						
SLS	63040	SLS	56905	SLS	62361	SLS	39351	SLS	42723	SLS	37844	SLS	42701	SLS	52829						
JAX-ROT	CHS-ROT	ELZ-ROT	G	JAX-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	NRF-ROT	NRF-ROT	ELZ-ROT	ELZ-ROT	G								
																					177.6
0802	22.4	0502	22.5	0402	22.7	0202	22.7	0102	22.6	0302	22.5	0502	22.6	0702	22.3						
SLS	54782	SLS	49824	SLS	44205	SLS	46946	SLS	52644	SLS	59963	SLS	55350	SLS	34360						
CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	ELZ-ROT	CHS-ROT	JAX-ROT	CHS-ROT										
																					180.3
0601	23.0	0401	23.0	0201	23.0	0101	23.0	0301	23.0	0501	23.0										
SLS	60230	SLS	47926	SLS	39798	SLS	37501	SLS	42837	SLS	48142										
CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT											
																					138.0
																					50.4
																					95.9
																					142.7
																					145.5
																					148.9
																					148.3
																					144.9
																					144.1
																					96.1
																					50.7
																					1167.5
																					TOTAL WT
																					583.4
																					CENTER LINE
																					.0
																					STBD
																					584.1
																					DIFF DIR
																					.7
																					STBD
																					PORT

HATCH LIST HATCH NO 06
 VESSEL SL MCLEAN
 PORT DEPARTURE OHV
 FINAL PLAN

SEA - LAND SERVICE I-N-C
 VOYAGE 012H
 DESTINATION ROT

MASTER
 DATE 04/08/73

PAGE NO 007

TABLE VI (Cont'd)

1009 15.3 SLS 29273 FLZ-ROTX G	0609 17.7 SLS 27178 ELZ-PTNX	0409 17.3 SLS 26170 ELZ-FELX	0209 19.1 SLS 29399 CHS-FELX	0109 19.5 SLS 26403 ELZ-PTNX	0309 18.5 SLS 29809 JAX-FELX	0909 16.2 SLS 26336 ELZ-PTNX	123.6			
1000 20.8 SLS 26740 ELZ-LHAX	0808 21.4 SLS 20499 ELZ-FELX	0608 21.7 SLS 21658 ELZ-FELX	0408 21.5 SLS 26199 ELZ-FELX	0208 23.2 SLS 28834 JAX-ROTX	0108 19.5 SLS 26962 ELZ-LHAX	0308 22.2 SLS 28619 JAX-ROTX	0508 17.5 SLS 21669 ELZ-ROTX	0708 21.2 SLS 26295 ELZ-LHAX	0908 19.9 SLS 20580 ELZ-ROTX	Removed for Cond. 4 208.9
36.1	21.4	39.4	38.8	42.3	39.0	40.7	17.5	21.2	36.1	332.5
PORT 178.0		CENTER LINE .0			STBD 154.5		DIFF DIR 23.5 PORT			TOTAL WT
Removed for Cond. 6										
0607 10.2 0407 12.7 0207 14.9 0107 19.2 0307 11.9 0507 11.2										
775158 SLS 58030 SLS 60668 SLS 67429 SLS 47476 SLS 69897										
ELZ-ROT G NRF-LHA NRF-PTN ELZ-PTN ELZ-ROT G ELZ-ROT G										
80.1										
0616 12.8 0406 11.9 0206 16.7 0106 15.5 0306 12.4 0506 12.7										
SLS 53040 SLS 72410 SLS 72972 SLS 59142 SLS 54584 SLS 68511										
CHO-ROT ELZ-LHA ELZ-PTN ELZ-PTN ELZ-ROT ELZ-ROT										
0906 5.9 SLS 15479 ELZ-LHA										
87.9										
0605 15.7 0405 15.7 0205 17.4 0105 13.5 0305 15.6 0505 15.7										
SLS 62827 SLS 52317 SLS 50330 300379 SLS 59107 SLS 58293										
JAX-ROT JAX-ROT NRF-PTN BOS-PTN NRF-ROT JAX-ROT										
0905 6.4 SLS 27300 ELZ-ROT G										
100.0										
0104 19.8 0604 16.1 0404 17.4 0204 18.3 0104 17.3 0304 15.8 0504 17.4										
SLS 70283 SLS 59147 SLS 62057 SLS 15035 SLS 35163 SLS 50003 SLS 59620										
BAL-FEL ELZ-ROT NRF-ROT ELZ-PTN BOS-PTN ELZ-ROT NRF-ROT										
0904 9.7 SLS 300438 ELZ-ROT G										
133.8										
0803 20.1 0603 17.5 0403 17.6 0203 19.9 0103 21.1 0303 17.6 0503 17.6 0703 22.4 0903 16.9										
302310 SLS 60678 SLS 40793 SLS 15810 SLS 62940 SLS 62971 SLS 54176 301787 301031										
ELZ-PTN NRF-ROT NRF-ROT ELZ-PTN LDC-PTN NRF-ROT NRF-ROT ELZ-ROT G ELZ-ROT G										
170.7										
0102 22.3 SLS 92850 ELZ-PTNTN										
0702 22.2 SLS 95854 ELZ-PTNTN										
0802 22.1 0602 20.3 0402 22.6 0202 22.3 0102 18.1 0302 20.8 0502 18.8 0702 22.5										
SLS 95844 SLS 55684 SLS 46188 SLS 60670 SLS 15753 SLS 35359 SLS 29078 SLS 95802										
ELZ-PTNTN CHS-ROT NRF-LHA ELZ-PTN ELZ-PTN CHS-PTN JAX-ROT ELZ-PTNTN										
212.0										
0401 21.3 0601 23.4 0401 21.8 0201 22.6 0101 22.5 0301 22.4 0501 22.5 0701 22.0										
SLS 67069 SLS 72254 SLS 64982 SLS 61994 SLS 56751 SLS 15439 SLS 70418 SLS 66619										
BAL-FEL MAY-ROT ELZ-LHA JAX-PTN JAX-PTN ELZ-PTN ELZ-ROT ELZ-ROT G										
178.5										
105.6	118.0	119.7	132.1	127.2	116.5	115.9	89.1	38.9	963.0	
PORT 475.4		CENTER LINE .0			STBD 487.6		DIFF DIR 12.2 STBD			TOTAL WT 1295.5

HATCH LIST HATCH NO 07 S E A - L A N D S E R V I C E I N C PAGE NO 008
 VESSEL SL MCLEAN VOYAGE 012M MASTER DATE 04/08/73
 PORT DEPARTURE OHV DESTINATION ROT
 FINAL PLAN

TABLE VI (Cont'd)

1010	5-2	0410	5-3	0610	5-5	0410	5-6	0210	5-7	0110	8-9	0310	5-7	0510	5-6	0710	5-3	0910	5-2	50.0		
SLS	30505	SLS	60235	SLS	36181	SLS	71365	SLS	62199	SLS	56822	SLS	55650	SLS	70757	SLS	66002	SLS	36748			
CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	ELZ-ROT	G	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT			
1059	16-5	0809	17-5	0609	18-0	0409	18-8	0209	18-8	0109	18-6	0309	18-6	0509	18-6	0709	17-8	0909	17-1	180.3		
SLS	200115	SLS	21431	SLS	21666		200599	SLS	29742		200547		200556		200189		200131		200540			
CHS-ROT	ELZ-ROT	G	CHS-ROT	CHS-ROT	CHS-ROT	NRF-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT			
1008	19-9	0808	19-9	0608	19-8	0408	19-8	0208	18-9	0108	18-8	0308	19-6	0508	19-7	0708	19-4	0908	18-9	194.7		
SLS	29907	SLS	200608	SLS	200544	SLS	26500		200488		200606		200543		200604		200647		200623			
CHS-ROT	ELZ-ROT	G	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT			
41-6	42-7	43-3	44-2	43-4	46-3	43-9	43-9	43-9	42-5	41-2	433.0	Removed for Cond. 4									433.0	TOTAL WT
										PORT	215.2	CENTER LINE	.0	STBD	217.6	DIFF	DIR	2.6	STBD			
1007	14-7	0807	11-7	0607	14-4	0407	14-1	0207	15-0	0107	14-8	0307	14-6	0507	11-0	0707	13-6	0907	14-8	138.7		
SLS	69326	SLS	15920	SLS	69765	SLS	65657	SLS	48412		301654	SLS	58649	SLS	61894	SLS	48022	SLS	54563			
CHS-ROT	ELZ-ROT	G	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT			
1006	15-9	0805	15-1	0606	15-9	0406	14-7	0206	19-7	0106	19-3	0306	15-7	0506	14-1	0706	15-9	0906	15-9	162.2		
SLS	45359	SLS	55087		300889	SLS	46184	SLS	43343		54573	SLS	73276	SLS	48625	SLS	65017	SLS	63159			
CHS-ROT	NRF-ROT		CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT			
1005	17-6	0405	16-5	0605	20-7	0405	19-7	0205	21-0	0105	22-1	0305	19-8	0505	20-7	0705	16-9	0905	17-8	188.8		
SLS	72954	SLS	30010	SLS	36978	SLS	34192	SLS	70824		61503		302235	SLS	46867	SLS	52297	SLS	42408			
CHS-ROT	CHS-ROT	NRF-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT			
1004	17-8	0804	17-7	0604	22-1	0404	22-1	0204	22-1	0104	20-8	0304	22-1	0504	22-0	0704	17-7	0904	17-8	202.2		
SLS	69781	SLS	62954	SLS	69281	SLS	56226	SLS	55822		41679	SLS	64603	SLS	51152	SLS	69985	SLS	56363			
CHS-ROT	NRF-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT			
1003	23-4	0803	23-1	0603	22-7	0403	22-8	0203	22-7	0103	22-5	0303	22-5	0503	22-7	0703	22-4	0903	22-5	225.3		
SLS	61814	SLS	301826	SLS	30662	SLS	40002	SLS	54146		60299	SLS	51889	SLS	47100	SLS	61664	SLS	67614			
CHS-ROT	JAX-ROT	JAX-ROT	JAX-ROT	JAX-ROT	JAX-ROT	JAX-ROT	JAX-ROT	JAX-ROT	JAX-ROT	JAX-ROT	JAX-ROT	JAX-ROT	JAX-ROT	JAX-ROT	JAX-ROT	JAX-ROT	JAX-ROT	JAX-ROT	JAX-ROT			
1002	23-1	0602	23-1	0602	22-7	0402	23-3	0202	23-3	0102	22-8	0302	23-3	0502	22-7	0702	22-5	0902	23-0	229.8		
SLS	50572	SLS	73523	SLS	54230	SLS	47503	SLS	39167		44732	SLS	44513	SLS	43032	SLS	68415	SLS	63870			
CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT	CHS-ROT			
0601	22-7	0601	23-0	0401	23-3	0201	23-3	0101	23-3	0501	22-8	0701	22-8	0901	22-8	0701	22-8	0701	22-8	1331.5		
SLS	73132	SLS	57606	SLS	50497	SLS	50965		69677	SLS	58539		304739		301237							
CHS-ROT	CHS-ROT	JAX-ROT	JAX-ROT	JAX-ROT	JAX-ROT	JAX-ROT	JAX-ROT	JAX-ROT	JAX-ROT	JAX-ROT	JAX-ROT	JAX-ROT	JAX-ROT	JAX-ROT	JAX-ROT	JAX-ROT	JAX-ROT	JAX-ROT	JAX-ROT			
111-5	128-9	141-5	136-0	147-1	145-6	141-3	136-0	131-6	111-8	1331.5	Removed for Cond. 5									1331.5	TOTAL WT	
										PORT	665.0	CENTER LINE	.0	STBD	666.5	DIFF	DIR	1.5	STBD			
																				1764.5		

HATCH LIST HATCH NO 10
 VESSEL SL MCLEAN
 PORT DEPARTURE BHV
 FINAL PLAN

SEA - LAND SERVICE INC
 VOYAGE 012W
 DESTINATION ROT

MASTER
 DATE 04/08/73

PAGE NO 011

TABLE VI (Cont'd)

1009 2.6	0209 2.5 0109 3.3	0909 3.3		
SLS 73389	SLS 70743 300779	300856		
EMPTY E	*EMPTY* E *EMPTY* E	*EMPTY* E	11.7	
1008 2.5	0208 2.6 0108 2.5	0908 2.4	Removed	
SLS 70803	SLS 74065 SLS 70277	SLS 64039	for	
EMPTY E	*EMPTY* E *EMPTY* E	*EMPTY* E	Cond. 4 10.0	
5.1	5.1 5.8	5.7	21.7	
PORT 10.2	CENTER LINE .0	STBD 11.5	DIFF DIR 1.3 STBD	TOTAL WT
<hr/>				
PORT .0	CENTER LINE .0	STBD .0	DIFF DIR .0 STBD	TOTAL WT 21.7
				Empty (All Conditions)

HATCH LIST HATCH NO 11 S E A - L A N D S E R V I C E I N G PAGE NO 012
 VESSEL SL 2CLEAN VOYAGE 012H MASTER DATE 04/08/73
 PORT DEPARTURE BHV DESTINATION ROT
 FINAL PLAN

TABLE VI (Cont'd)

LINE	DESCRIPTION	DATE	TIME	STBD	DIR	STBD	DIR	TOTAL WT		
1010	5-8 0810 5-9 0610 6-2 0410 6-5 0210 7-6 0110 8-3 0310 7-6 0510 6-5 0710 6-1 0910 5-9									
SLS	69449 SLS 62049 SLS 60101 SLS 72442 SLS 42425 SLS 60665 SLS 61465 SLS 42815 SLS 55191									
ELZ-ROT	CHS-ROT CHS-ROT CHS-ROT CHS-ROT CHS-ROT CHS-ROT CHS-ROT CHS-ROT CHS-ROT							66.4		
1009	20-1 0809 20-3 0609 20-2 0409 20-6 0109 20-6 0309 20-4 0509 20-3 0709 20-2 0909 20-1									
SLS	200611 SLS 26821 200624 200493 200640 200646 200639 200108 200625 200613							206.1		
NRF-ROT	NRF-ROT NRF-ROT NRF-ROT NRF-ROT NRF-ROT NRF-ROT NRF-ROT NRF-ROT NRF-ROT									
1008	21-2 0808 21-5 0608 22-3 0408 22-6 0208 21-6 0109 20-8 0308 22-3 0508 21-6 0708 21-5 0908 20-9									
SLS	26830 SLS 29036 SLS 28022 SLS 22185 SLS 20342 SLS 25716 SLS 26375 SLS 21524 SLS 29162 SLS 26684									
JAX-ROT	JAX-ROT ELZ-ROT JAX-ROT ELZ-ROT JAX-ROT ELZ-ROT JAX-ROT ELZ-ROT JAX-ROT ELZ-ROT							216.3		
47.1	47.7	48.7	49.4	49.8	49.7	50.3	48.4	47.8	46.9	485.8

Removed for Cond. 5

LINE	DESCRIPTION	DATE	TIME	STBD	DIR	STBD	DIR	TOTAL WT		
1007	17-5 0807 18-3 0607 15-6 0407 15-0 0207 11-0 0107 8-1 0307 14-1 0507 9-6 0707 22-6 0907 18-4									
SLS	63956 SLS 63285 SLS 37817 SLS 39551 SLS 37876 SLS 46251 SLS 32360 SLS 72190 SLS 17656 SLS 55339									
NRF-LEG	NRF-LEG CHS-GOA NRF-GOA NRF-GOA 5AL-GOA NRF-GOA BAL-GOA JAX-GOA BAL-GOA JAX-CDZ NRF-LEG							150.2		
1006	18-7 0806 19-6 0606 17-0 0406 16-0 0206 15-9 0106 15-7 0306 15-9 0506 15-7 0706 17-3 0906 19-2									
SLS	46958 SLS 46707 SLS 71928 SLS 35595 SLS 37052 SLS 64802 SLS 73129 SLS 17561 SLS 27388 SLS 27349									
NRF-LEG	NRF-LEG NRF-GOA NRF-GOA NRF-GOA NRF-GOA CHS-GOA JAX-GOA NRF-LEG NRF-LEG NRF-LEG							172.1		
1005	19-9 0805 20-3 0605 20-1 0205 18-0 0105 17-4 0305 20-0 0505 17-7 0705 15-7 0905 20-8									
SLS	52839 SLS 55440 SLS 48994 SLS 54579 SLS 68347 SLS 36637 SLS 25107 SLS 71066 SLS 41226 SLS 35915									
NRF-LEG	CHS-LEG BAL-GOA JAX-GOA NRF-GOA NRF-GOA BAL-GOA NRF-GOA CHS-GOA CHS-GOA							190.2		
1004	20-7 0804 20-8 0604 22-2 0404 22-2 0204 21-0 0104 23-6 0304 21-7 0504 22-4 0704 20-5 0904 22-3									
SLS	53634 SLS 61209 SLS 25046 SLS 25057 SLS 44470 SLS 25066 SLS 52071 SLS 35496 SLS 71576 SLS 71490									
CHS-LEG	CHS-LEG BAL-GOA BAL-GOA BAL-GOA JAX-GOA BAL-GOA NRF-GOA CHS-GOA CHS-GOA CHS-GOA							214.4		
1003	21-4 0803 21-5 0603 23-1 0403 23-0 0203 22-7 0103 22-3 0303 22-7 0503 20-9 0703 22-2 0903 20-5									
SLS	50190 SLS 43510 302103 SLS 62034 SLS 66373 SLS 47039 SLS 69481 SLS 33631 SLS 54817 SLS 55630									
CHS-LEG	CHS-LEG CHS-GOA CHS-GOA CHS-GOA CHS-GOA NRF-GOA CHS-GOA NRF-GOA NRF-GOA NRF-LEG							220.3		
98.2	100.5	98.2	96.3	88.6	84.1	94.4	86.3	98.8	101.8	947.2

TOTAL WT 1433.0
 PORT 481.8
 STBD 465.4
 DIFF DIR 16.4 PORT

HATCH LIST HATCH NO 08
 VESSEL SL MCLEAN
 PORT DEPARTURE BHV
 FINAL PLAN

SEA - LAND SERVICE INC
 VOYAGE 012H
 DESTINATION ROT

MASTER
 DATE 04/08/73

PAGE NO 009

TABLE VI (Cont'd)

PORT	CENTER LINE	STBD	DIFF DIR	TOTAL WT
1010 10.2 0810 10.3 0610 9.4 0410 23.4 0210 23.4 0110 13.4 103466 103464 501579 101461 100654 100010 BAL-ROT4 BAL-ROT4 HAM-HOU4 GRA-ROT4 GRA-ROT4 HAM-HOU4 0510 5.1 0710 5.7 0910 5.0 101515 871340 100987 ELZ-ROT4 BHV-HOU4 ELZ-ROT4	105.9			
1009 11.8 0809 11.5 0609 8.4 0409 9.3 0209 9.7 0109 8.1 0309 8.6 0509 7.2 0709 6.9 0909 8.1 103458 872376 103603 424792 986027 424179 420546 902404 101353 872665 BAL-ROT4 ELZ-FEL4 BAL-FEL4 BHV-HOU4 PAK-HOU4 BHV-HOU4 BHV-HOU4 BHV-HOU4 ELZ-FEL4 ELZ-FEL4	89.6			
1008 8.9 0808 11.4 0608 11.9 0408 13.3 0208 9.3 0108 7.1 0308 6.6 0508 8.4 0708 9.4 0908 11.3 101220 101302 101987 422515 100905 101179 100080 101687 100924 423368 ELZ-FEL4 ELZ-ROT4 M ELZ-LHA4 ELZ-FEL4 ELZ-FEL4 ELZ-ROT4 ELZ-ROT4 ELZ-FEL4 ELZ-FEL4 BHV-HOU4	Removed for Cond. 4 97.6			
30.9 33.2 29.7 46.0 42.4 26.6 15.2 20.7 22.0 24.4				293.1
	PORT 182.2	CENTER LINE .0	STBD 110.9 DIFF DIR 71.3 PORT	TOTAL WT
Removed for Cond. 6				
1007 20.6 0807 15.1 0607 11.5 0407 16.5 0207 18.3 424496 103473 604481 605042 101913 ELZ-ROT4 BAL-ROT4 BHV-HOU4 BHV-HOU4 ELZ-ROT4RG 0107 18.1 0307 19.3 0507 21.5 0707 19.2 0907 16.2 100380 101639 428199 103529 100610 ELZ-ROT4 ELZ-ROT4 G ELZ-ROT4 ELZ-ROT4 ELZ-FEL4	176.3			
1006 15.0 0806 18.3 0606 13.4 0406 17.8 0206 19.1 101350 872614 872401 100122 101131 ELZ-FEL4 ELZ-ROT4 G BHV-HOU4 BHV-HOU4 S05-ROT4 0106 18.1 0306 20.9 0506 21.0 0706 20.7 0906 21.7 100287 100305 100949 100008 601363 ELZ-FEL4 ELZ-ROT4 G ELZ-ROT4 G ELZ-ROT4 ELZ-FEL4	186.0			
1005 17.3 0805 18.9 0605 13.4 0405 17.4 0205 18.7 100700 903825 601339 790909 101824 ELZ-ROT4 PHL-ROT4 BHV-HOU4 HAM-HOU4 ELZ-ROT4 G 0105 18.3 0305 18.4 0505 22.1 0705 20.5 0905 21.0 100609 100275 100150 101005 600228 ELZ-ROT4 BAL-ROT4 ELZ-ROT4 ELZ-ROT4 ELZ-ROT4 G	186.0			
1004 18.3 0804 20.0 0604 14.2 0404 18.3 0204 19.4 100523 100117 600227 707868 100713 ELZ-ROT4 G ELZ-ROT4 G BHV-HOU4 HAM-HOU4 ELZ-ROT4 G 0104 19.4 0304 19.4 0504 22.9 0704 22.1 0904 19.4 100366 101493 100456 101015 101842 ELZ-ROT4 G ELZ-ROT4 ELZ-LHA4Y ELZ-ROT4 ELZ-PTN4R	193.4			
1003 20.1 0803 20.7 0603 15.0 0403 13.6 0203 19.9 101647 101087 421638 901413 100061 BAL-ROT4 BAL-ROT4 HAM-HOU4 HAM-HOU4 ELZ-ROT4 0103 19.8 0303 21.1 0503 22.1 0703 22.0 0903 21.7 101535 100761 100679 100244 427358 ELZ-FEL4 ELZ-ROT4 G ELZ-ROT4 ELZ-ROT4 ELZ-ROT4 G	196.0			
1002 21.1 0802 22.0 0602 15.0 0402 18.5 0202 20.5 103322 605030 501517 701466 100271 ELZ-ROT4 ELZ-ROT4 HAM-HOU4 HAM-HOU4 ELZ-FEL4 0102 20.1 0302 21.0 0502 22.1 0702 20.4 0902 17.6 101163 601312 901284 101415 604249 ELZ-ROT4 G BAL-FEL4 ELZ-LHA4Y ELZ-ROT4 G ELZ-ROT4 G	197.7			
1001 22.8 0801 22.3 0601 14.8 0401 18.5 0201 21.0 960357 903750 903846 904345 101263 BAL-ROT4 ELZ-ROT4 HAM-HOU4 HAM-HOU4 ELZ-LHA4 0101 20.7 0301 23.0 0501 23.7 0701 20.6 0901 19.2 100288 100136 100701 627295 100624 ELZ-FEL4 ELZ-ROT4RG ELZ-ROT4 ELZ-ROT4 ELZ-ROT4	206.6			
135.2 137.3 97.3 120.6 136.9 134.5 143.1 155.4 145.5 136.2				1342.0
	PORT 627.3	CENTER LINE .0	STBD 714.7 DIFF DIR 87.4 STBD	TOTAL WT 1635.1

HATCH LIST HATCH NO 12
 VESSEL SL MCLEAN
 PORT DEPARTURE BHV
 FINAL PLAN

SEA - LAND SERVICE INC
 VOYAGE 012W
 DESTINATION ROT

MASTER
 DATE 04/08/73

PAGE NO 013

TABLE VI (Cont'd)

1010	8.9	0810	12.3	0610	12.1	0410	12.3	0210	6.5	0110	8.9	0310	12.7		0710	12.0	0910	12.3				
	100087		100633		100517		101042	SLS 47650		101140		100718				101190		100688				
ELZ-FEL4	ELZ-FEL4	ELZ-PTN4	ELZ-FEL4	ELZ-PTN4	ELZ-FEL4	ELZ-PTN4	ELZ-FEL4	ELZ-PTN4	ELZ-FEL4	ELZ-ROT4	ELZ-ROT4	ELZ-ROT4	ELZ-ROT4		ELZ-LHA4	ELZ-FEL4					98.8	
1009	14.9	0809	17.0	0609	17.4	0409	17.7	0209	24.0	0109	18.3	0309	2.3		0709	17.3	0909	15.0				
	SLS 23134		200238	SLS 23299		200046	SLS 27387	SLS 26297	SLS 44196						SLS 23176		200003					
ELZ-ROT4	ELZ-ROT4	ELZ-ROT4	ELZ-ROT4	ELZ-ROT4	PAP-LHAV	ELZ-ROT4	*EMPTY*	E						ELZ-ROT4	ELZ-PTN4						143.9	
1008	10.3	0808	18.8	0608	19.5	0408	21.7	0208	24.5	0108	22.9	0308	21.9	0508	19.5	0708	19.0	0908	18.3			
	SLS 26635	SLS 26567	SLS 23041	SLS 20656	SLS 89625	SLS 29371	SLS 28895	SLS 23194	SLS 29042	SLS 26164												
ELZ-ROT4	JAX-FEL4	ELZ-LHAX	ELZ-FEL4	ELZ-EL4	ELZ-FEL4	ELZ-FEL4	ELZ-FEL4	ELZ-LHAX	BAL-ROT4	ELZ-ROT4											Removed for Cond. 3	
	42.1	48.1	49.0	51.7	55.0	50.1	36.9	19.5	49.1	45.6											447.1	
	PORT		CENTER LINE				STBD		DIFF DIR		PORT		TOTAL WT									
	245.9		.0				201.2		46.7		PORT											

Removed for Cond. 6

1007	2.5	0807	2.5	0607	2.5	0407	7.0	0207	11.2	0107	8.7	0307	4.8	0507	2.5	0707	2.5	0907	2.5			
	SLS 59948	SLS 51273	SLS 39608	SLS 51194	SLS 37912					SLS 47816	SLS 45950	SLS 53080	SLS 40865	SLS 39566								
EMPTY	E	*EMPTY*	E	*EMPTY*	E	BAL-LEG	JAX-BCL			ELZ-GR4	NRF-LEG	*EMPTY*	E	*EMPTY*	E	*EMPTY*	E	*EMPTY*	E		46.7	
1006	2.5	0806	2.5	0606	2.5	0406	13.4	0206	11.9	0106	13.5	0306	11.6	0506	2.6	0706	2.6	0906	2.5			
	SLS 70879	SLS 73472	SLS 45887	SLS 63785	300714					SLS 62733	SLS 46972	300385	301318	SLS 45827								
EMPTY	E	*EMPTY*	E	*EMPTY*	E	CHS-LEG	NRF-BCL			NRF-VAL	NRF-LEG	*EMPTY*	E	*EMPTY*	E	*EMPTY*	E	*EMPTY*	E		65.6	
1005	2.6	0805	2.6	0605	13.5	0405	13.6	0205	16.2	0105	14.5	0305	15.9	0505	14.1	0705	2.5	0905	2.5			
	300464	300789	SLS 72949	SLS 42690	SLS 43265					SLS 65219	SLS 70837	SLS 63584	SLS 37574	SLS 62367								
EMPTY	E	*EMPTY*	E	ELZ-LEG	NRF-LEG	NRF-BCL				BAL-VAL	NRF-BCL	ELZ-LEG	*EMPTY*	E	*EMPTY*	E	*EMPTY*	E			98.0	
0804	15.4	0604	14.1	0404	13.9	0204	16.6			0104	15.4	0304	16.2	0504	13.6	0704	15.7					
	SLS 44971	SLS 60994	SLS 52215	SLS 69127						SLS 51663	SLS 31337	SLS 72092	SLS 53851									
ELZ-LEG	ELZ-LEG	JAX-LEG	NRF-BCL							CHS-VAL	ELZ-BCL	NRF-LEG	ELZ-LEG								120.9	
0803	15.8	0603	17.1	0403	16.8	0203	17.5			0103	17.4	0303	17.0	0503	14.0	0703	17.8					
	SLS 38895	SLS 33832	SLS 47694	SLS 63772						SLS 49746	SLS 35511	SLS 52960	SLS 52886									
ELZ-VAL	ELZ-LEG	NRF-LEG	NRF-MAP							BOS-VAL	NRF-BCL	NRF-LEG	ELZ-VAL								133.4	
	7.6	38.8	49.7	64.7	73.4	69.5	65.5	46.8	41.1	7.5											464.6	
	PORT		CENTER LINE				STBD		DIFF DIR		PORT		TOTAL WT									
	234.2		.0				230.4		3.8		PORT											

MASTER DATE 04/08/73

S E A - L A N D S E R V I C E I N C

HATCH LIST HATCH NO 13
 VESSEL SL MCLEAN
 PORT DEPARTURE BNY
 FINAL PLAN

TABLE VI (Cont'd)

VOYAGE	DESTINATION	ROT	STBD	DIFF DIR	TOTAL WT	
0309	21-7 0209	20-3 0109	17-9 0309	20-3 0509	19-5 0709	18-2
SLS 22595	SLS 21580	SLS 21215	SLS 28197	SLS 26912	SLS 20507	200032
NRF-FELX	JAX-FELX	60S-FELX	ELZ-FELX	ELZ-FELX	KNG-FELX	153-7
0808	23-2 0408	22-6 0208	22-1 0108	22-4 0308	22-6 0509	22-6 0708
SLS 20914	SLS 23037	SLS 26021	SLS 29827	SLS 28586	SLS 26194	SLS 28848
KNG-FELX	JAX-FELX	JAX-FELX	ELZ-ROTX	KNG-FELX	JAX-FELX	JAX-FELX
37-4	45-5	44-3	42-4	40-3	42-1	40-8
PORT	CENTER LINE	STBD	DIFF DIR	TOTAL WT		
169-6	.0	166-1	3-5	395-7		

Removed for Cond. 3

Removed for Cond. 5

0807	10-3 0637	9-6	0507	6-6 0707	10-1
SLS 301145	SLS 73345		SLS 70215	SLS 41691	
ELZ-ROTX	G ELZ-ROTX		CHS-FEL	ELZ-ROTX	36-6
0806	14-5 0606	9-8 0406	13-7	0506	13-7 0706
SLS 301738	SLS 72955	SLS 38747		SLS 50357	SLS 71473
CHS-ROTX	ELZ-ROTX	G BOS-FEL		BOS-FEL	CHS-ROTX
0805	17-6 0605	19-1 0405	18-0	0505	18-9 0705
SLS 56669	SLS 60857	SLS 54009		SLS 36837	SLS 21461
NRF-ROTX	BOS-FEL	ELZ-FEL		ELZ-FEL	ELZ-ROTX
0804	22-5 0604	20-2 0404	19-4	0504	19-5 0704
SLS 73304	SLS 47827	SLS 63439		SLS 47941	SLS 63859
CHS-ROTX	LRC-FEL	ELZ-FELX		LBC-FEL	ELZ-ROTX
0803	22-5 0403	20-4	0103	17-6	0503
SLS 51253	SLS 48548		SLS 61093		SLS 61093
ELZ-FEL	LBC-FEL		ELZ-FELX		ELZ-FELX
64-9	61-2	71-5	33-8	79-4	62-1
PORT	CENTER LINE	STBD	DIFF DIR	TOTAL WT	
217-6	.0	175-3	42-3	728-6	

HATCH LIST HATCH NO 14
 VESSEL SL MCLEAN
 PORT DEPARTURE BHV
 FINAL PLAN

SEA-LAND SERVICE INC
 VOYAGE 012W
 DESTINATION ROT

MASTER
 DATE 04/08/73

PAGE NO 015

TABLE VI (Cont'd)

0610 8.1	0210 9.9 0110 10.9	0710 7.4				
102233	100316 101015	100420				
ELZ-FEL4	ELZ-ROT4 NRF-ROT4	ELZ-ROT4				36.3
0809 2.4	0209 2.6 0109 2.6	0709 2.5				
SLS 60884	SLS 72504 SLS 73996	SLS 70737				
EMPTY E	*EMPTY* E *EMPTY* E	*EMPTY* E				10.1
0808 2.4	0208 2.4 0108 14.9 0308 17.7	0708 14.7				
SLS 54033	SLS 59290 200551 SLS 28711	SLS 28988				
EMPTY E	*EMPTY* E NRF-ROTX BHV-FELX	NRF-ROTX			Removed for Cond. 3	52.1
12.9	14.9	28.4	17.7	24.6		98.5
PORT 27.8	CENTER LINE .0	STBD 70.7	DIFF 42.9	DIR STBD		TOTAL WT
PORT .0	CENTER LINE .0	STBD .0	DIFF .0	DIR STBD		TOTAL WT
					Empty (All-Conditions)	98.5

HATCH LIST HATCH NO 15
 VESSEL SL MCLEAN
 PORT DEPARTURE BHV
 FINAL PLAN

SEA - LAND SERVICE INC
 VOYAGE 012W
 DESTINATION ROT

MASTER
 DATE 04/09/73

PAGE NO 016

TABLE VI (Concluded)

0609 2.4 SLS 53667 *EMPTY* E	0209 11.7 0109 18.6 200068 SLS 23695 ELZ-LHAX ELZ-LHAX	0509 2.4 SLS 56367 *EMPTY* E			35.1
0608 18.0 SLS 23167 ELZ-ROTX	0208 18.5 0108 21.9 SLS 23106 SLS 20695 ELZ-LHAX ELZ-FELX	0508 22.6 SLS 28948 ELZ-FELX		Removed for Cond. 3	81.0
20.4	30.2	40.5	25.0		176.1
PORT -50.6	CENTER LINE .0	STBD 65.5	DIFF DIR 14.9 STBD		TOTAL WT
Removed for Cond. 5					
	0207 2.2 SLS 34065 *EMPTY* E	0107 2.4 SLS 46477 *EMPTY* E			4.6
	0206 2.2 SLS 36140 *EMPTY* E	0106 2.2 0306 3.3 SLS 33966 SLS 17320 *EMPTY* E *EMPTY* E			7.7
0405 7.6 0205 2.4 300037 SLS 46455 BHV-FEL *EMPTY* E	0105 2.4 0305 2.4 SLS 59595 SLS 16116 *EMPTY* E *EMPTY* E				14.8
7.6	6.8	7.0	5.7		27.1
PORT 14.4	CENTER LINE .0	STBD 12.7	DIFF DIR 1.7 PORT		TOTAL WT 143.2

TABLE VII

SUMMARY OF REDUCED STRAIN DATA
 CALIBRATION EXPERIMENT
 SEA-LAND McLEAN

Sensor No.	Sensor Ident.	Quantity	Condition (1)							Units
			1	3	4	5	6	7		
1	LVB	Stress	530	-618	397	1104	1413	2649	psi	
2	TSM	Shear	0	0	183	882	1156	-304	psi	
11	LHB	Stress	-530	-530	-574	-1236	-1501	-751	psi	
12	SFP	Shear	-171	171	-445	-651	-616	-1507	psi	
13	SFS	Shear	-28	527	-56	-695	-945	-1417	psi	
15	LSTS	Stress	450	-1306	-1036	-45	630	2702	psi	
16	LSMS	Stress	-78	-1616	38	2746	3319	2518	psi	
17	LSBS	Stress	-229	1556	1419	732	870	-46	psi	
18	LSTP	Stress	225	-1144	137	1007	1511	2014	psi	
19	LSNP	Stress	0	0	479	287	479	575	psi	
20	LSBP	Stress	-272	317	181	0	317	-46	psi	
21	SAP	Shear	-284	682	511	568	739	369	psi	
22	SAS	Shear	0	-927	-702	-449	-393	-253	psi	
27	BGST	Shear	0	167	167	-250	-556	-111	psi	
28	BGSB	Shear	-28	0	111	56	139	250	psi	
30	ARLA	Stress	703	110	494	1920	2194	-55	psi	
31	ARIB	Stress	418	-232	836	4089	4554	0	psi	
32	ARIC	Stress	0	0	279	1115	1394	0	psi	
-	ARI	$\sigma_1(2)$	671	302	896	4141	4670	-8.0	psi	
-	ARI	$\sigma_2(2)$	167	-152	172	71.9	310	-71	psi	
-	ARI	$\theta(2)$	10.5	-39.7	38.3	40.5	40.9	67.5	deg.	

TABLE VII (Continued)

VII-2

Sensor No.	Sensor Nomen.	Quantity	Condition (1)						Units
			1	3	4	5	6	7	
33	AR2A	Stress	781	725	1729	-446	-2063	335	psi
34	AR2B	Stress	58	1109	0	759	1050	-234	psi
35	AR2C	Stress	-330	-1489	279	-992	-1820	-165	psi
-	AR2	σ_1	766	918	2358	174.5	-359	432	psi
-	AR2	σ_2	-141	-1980	425	-2166	-5029	-199	psi
-	AR2	θ	-8.4	26.7	-27.0	39.8	46.2	-26.0	deg.
36	AR3A	Stress	-342	-1426	1540	-855	-2281	570	psi
37	AR3B	Stress	226	-225	621	-733	-1409	508	psi
38	AR3C	Stress	-223	-781	-112	-558	-781	-223	psi
-	AR3	σ_1	6.1	-801	1639	-864	-1532	645	psi
-	AR3	σ_2	-794	-2262	340	-1099	-2718	-166	psi
-	AR3	θ	48.3	55.1	-3.3	-85.1	85.5	20.0	deg.
39	AR4A	Stress	-654	-2618	-1636	709	491	-54	psi
40	AR4B	Stress	223	-390	-167	168	223	502	psi
41	AR4C	Stress	1227	2119	1673	502	892	279	psi
-	AR4	σ_1	1134	1506	1324	1190	1354	746	psi
-	AR4	σ_2	-338	-2198	-1274	489	563	475	psi
-	AR4	θ	-88.1	-88.3	-86.8	-38.3	-56.7	10.9	deg.
43	R1A	Stress	226	-711	-108	-1644	-2192	-876	psi
44	R1B	Stress	233	279	233	-232	-557	-96	psi
45	R1C	Stress	167	279	-233	0	0	-233	psi
-	R1	σ_1	351	247	85.7	-351	567	-293	psi
-	R1	σ_2	262	-847	-544	-1933	-2475	-1232	psi
-	R1	θ	6.8	67.5	40.9	72.1	76.9	61.5	deg.

TABLE VII (Continued)

VII-3

Sensor No.	Sensor Nomen.	Quantity	Condition (1)						Units
			1	3	4	5	6	7	
46	R2A	Stress	390	-335	-1172	780	1338	725	psi
47	R2B	Stress	467	-350	-1226	-117	175	-292	psi
48	R2C	Stress	-276	-55	-276	-276	55	-276	psi
-	R2	σ_1	491	-108	-478	853	1513	874.3	psi
-	R2	σ_2	-332	-434	-1530	-153	320	-249.3	psi
-	R2	θ	25.4	-65.7	-65.8	-17.5	-19.6	-22.9	deg.
49	R3A	Stress	285	-228	-1540	285	628	484	psi
50	R3B	Stress	-451	-169	-1184	-677	-225	-225	psi
51	R3C	Stress	223	279	0	0	390	0	psi
-	R3	σ_1	674	9.8	-657	630	1070	610	psi
-	R3	σ_2	-278	-247	-1789	-543	33.7	-206	psi
-	R3	θ	-38	-75	-77.7	-35.1	-34.9	-22.6	deg.
52	R4A	Stress	818	655	436	-327	-436	382	psi
53	R4B	Stress	634	1056	792	-211	-528	0	psi
54	R4C	Stress	-167	335	502	279	0	-446	psi
-	R4	σ_1	904	1142	904	243	-6.0	279	psi
-	R4	σ_2	0	220	396	-510	-598	-367	psi
-	R4	θ	16.0	37.0	47.9	-74.4	-62.5	2.2	deg.
55	R5A	Stress	(243)	768	384	55	0	55	psi
56	R5B	Stress	(-176)	140	418	-232	-418	-464	psi
57	R5C	Stress	(-614)	-1060	187	-279	-502	-725	psi
-	R5	σ_1	(78)	546	524	3.4	-113	-143	psi
-	R5	σ_2	(-390)	-950	243	-316	-583	-784	psi
-	R5	θ	(0.7)	8.7	26.6	-17.7	-16.8	-9.1	deg.

TABLE VII (Continued)

VII-4

Sensor No.	Sensor Nomen.	Quantity	Condition (1)						Units
			1	3	4	5	6	7	
58	R6A	Stress	(1562)	223	112	0	0	223	psi
59	R6B	Stress	(21)	59	351	-350	-873	-583	psi
60	R6C	Stress	(-462)	-331	551	-331	-276	-717	psi
-	R6	σ_1	(1654)	162	631	-36.6	393	110	psi
-	R6	σ_2	(-129)	-308	290	-422	-776	-794	psi
-	R6	θ	(-365)	11.3	-24.0	39.7	-39.7	-17.8	deg.
61	R7A	Stress	(-365)	-1254	-1026	913	1255	628	psi
62	R7B	Stress	(0)	-3102	-1297	1635	2312	846	psi
63	R7C	Stress	(-433)	-1283	-614	167	390	-502	psi
-	R7	σ_1	(-318)	-327	-733	1651	2352	841	psi
-	R7	σ_2	(-790)	-3194	-1546	-151	-69	-666	psi
-	R7	θ	(-41.9)	-44.8	56.6	33.6	36.9	27.1	deg.
64	R8A	Stress	(-1173)	-2510	-1691	927	1582	982	psi
65	R8B	Stress	(-812)	-1743	-1162	212	687	0	psi
66	R8C	Stress	(-39)	265	317	-158	-264	-792	psi
-	R8	σ_1	(-370)	-373	-89	979	1636	838	psi
-	R8	σ_2	(-1313)	-2748	-1824	88	194	-565	psi
-	R8	θ	(-80)	-78.0	-77.3	-8.9	-8.8	-3.0	deg.
67	R9A	Stress	(639)	-55	-329	438	548	1755	psi
68	R9B	Stress	(101)	214	72	72	-116	401	psi
69	R9C	Stress	(-307)	223	390	223	390	-112	psi
-	R9	σ_1	(604)	268	325	680	1112	1941	psi
-	R9	σ_2	(-141)	-30	241	241	192	342	psi
-	R9	θ	(-3.9)	-68.5	-68.5	-33.8	-41.1	-12.1	deg.

TABLE VII (Continued)

VII-5

Sensor No.	Sensor Nomen.	Quantity	Condition (1)							Units
			1	3	4	5	6	7		
70	R10A	Stress	-	-	-	-	-	-	-	psi
71	R10B	Stress	(-87)	377	143	-499	-965	-1199		psi
72	R10C	Stress	(-1110)	-441	496	-166	-221	-552		psi
-	R10	σ_1	-	-	-	-	-	-		psi
-	R10	σ_2	-	-	-	-	-	-		psi
-	R10	θ	-	-	-	-	-	-		deg.
73	R11A	Stress	(286)	171	-57	171	685	1084		psi
74	R11B	Stress	(502)	226	959	226	0	508		psi
75	R11C	Stress	(-321)	-502	112	-167	56	-223		psi
-	R11	σ_1	(445)	172.5	767	1940	892	1110		psi
-	R11	σ_2	(-495)	-635	-692	464	133	81		psi
-	R11	θ	(29.9)	24.6	47.6	-68.6	-24.8	3.4		deg.
76	R12A	Stress	(77)	0	219	764	764	873		psi
77	R12B	Stress	(-1031)	-2536	-106	2588	2853	0		psi
78	R12C	Stress		-1473	218	1364	1255	-491		psi
-	R12	σ_1	(141)	495	557	2688	2854	1403		psi
-	R12	σ_2	(-1111)	-2541	51	262	-54	-875		psi
-	R12	θ	(-29.0)	-33.7	-44.9	70.7	48.8	31.0		deg.
79	R13A	Stress	(-1008)	-2084	-932	1645	2249	2139		psi
80	R13B	Stress	(-678)	-1379	-357	665	851	-78		psi
81	R13C	Stress	(182)	558	781	112	-55	-836		psi
-	R13	σ_1	(-64)	79	599	1845	2445	2200		psi
-	R13	σ_2	(-1082)	-2196	-808	601	605	-388		psi
-	R13	θ	(-78.0)	-77.5	-80.9	-7.8	-6.0	-13.1		deg.

TABLE VII (Continued)

VII-6

Sensor No.	Sensor Nomen.	Quantity	Condition (1)						Units
			1	3	4	5	6	7	
82	R14A	Stress	(1143)	-725	111	836	948	2007	psi
83	R14B	Stress	(45)	231	288	346	231	-115	psi
84	R14C	Stress	(44)	819	546	-163	-109	-709	psi
-	R14	σ_1	(1432)	686	629	856	1021	2120	psi
-	R14	σ_2	(218)	-552	283	78	145	-316	psi
-	R14	θ	(-22.5)	83	-84.7	-0.5	-9.8	-14.7	deg.
86	TGFS1	Stress	(1363)	-713	658	-1536	-2249	-1536	psi
87	HLST	Stress	-987	713	392	-110	-55	-55	psi
88	TGFS2	Stress	(995)	2092	1441	(-1263)	(-2393)	47	psi
89	HLSSB	Stress	419	279	233	-325	-697	-604	psi
90	TGFS3	Stress	(1171)	1283	279	502	1283	-279	psi
91	HLSPPT	Stress	1060	2119	2677	2733	2733	2956	psi
92	TGFS4	Stress	(-1060)	-1506	-1673	1115	2398	-948	psi
93	HLSPB	Stress	-725	-613	-836	-167	223	-446	psi
94	TGMS1	Stress	-759	-292	1692	-350	-1342	1809	psi
95	TGMS2	Stress	772	1765	1158	-2261	-1269	-828	psi
96	TGMS3	Stress	1483	1711	799	1141	1597	0	psi
97	TGMS4	Stress	-2426	-2030	-1410	1804	2819	-452	psi
98	TGMS1X	Stress	(1012)	2334	1692	-409	-876	1050	psi
99	TGMS2X	Stress	(1422)	2647	993	801	-110	938	psi
100	TGMS3X	Stress	(422)	798	57	-400	57	-571	psi
101	TGMS4X	Stress	(-925)	(-2807)	-677	112	225	169	psi
102	TGSS1X	Shear	(-147)	-95	-236	-165	-95	-448	psi
103	TGSS2X	Shear	(635)	874	172	-1275	-990	-1231	psi

TABLE VII (Concluded)

Sensor No.	Sensor Nomen.	Quantity	Condition (1)					Units	
			1	3	4	5	6		7
104	TGSS3X	Shear	-1378)	-2027	-3915	-5020	(-6456)	-2441	psi
105	TGSSdX	Shear	(770)	553	737	783	1520	1106	psi
106	TGAS1	Stress	-2677	-2454	-4685	-4852	-5354	-3179	psi
107	TGAS2	Stress	-	-	-	-	-	-	psi
108	TGAS3	Stress	1171	2621	1115	613	836	-279	psi
109	TGAS4	Stress	-669	725	223	1338	1785	-	psi
Fort	Scratch	Stress	690	1380	0	-690	-1380	-2760	psi
Stbd	Scratch	Stress	-650	1300	-650	-650	1300	-2600	psi
Added	SYA	Stress*	-	-4200	0*	-7050	-10200	-300	psi
Added	SYB	Stress*	-	-3600	0*	-6300	-8100	-1800	psi
Added	SYC	Stress*	-	-2100	0*	-1500	-2700	-1350	psi


NOTES: (1) All data except * assumes instrumentation zero to be condition 0 (coming up Mass River). All data manually reduced from oscillographs produced from analog magnetic tape except () which is meter reading.

- (2) σ_1 is maximum principal normal stress
 σ_2 is minimum principal normal stress
 θ is angle from "A" gage to principal axis

TABLE VIII
HATCH MEASUREMENTS

<u>Condition</u>	<u>Direction</u>	<u>Measurement</u>	<u>Cumulative Change</u>
4	1-1	96' 4 3/4"	0
4	2-2	96' 4 9/16"	0
4	3-3	50' 5"	0
4	4-4	50' 4 1/4"	0
5	1-1	96' 4 5/8"	- 1/8
5	2-2	96' 4 5/8"	+ 1/16
5	3-3	50' 4 3/4"	- 1/4
5	4-4	-*	-*
6	1-1	96' 4 3/8"	- 3/8
6	2-2	96' 4 15/16"	+ 3/8
6	3-3	50' 4 11/16"	- 5/16
6	4-4	-*	-*

HATCH 7



* Reading not taken due to safety considerations.

TABLE IX
SEA-LAND McLEAN CALIBRATION RESULTS
CALCULATED BENDING MOMENTS, SHEAR FORCES, AND NORMAL STRESSES

FRAME	COND.	M_b	ΔM_b	F_s	ΔF_s	Z_T	Z_B	n.a.	σ_T	$\Delta \sigma_T$	σ_B	$\Delta \sigma_B$		
		10^6 IN-LB	10^6 IN-LB	10^5 LB	10^6 LB	10^6 IN ³	10^6 IN ³	IN	PSI	PSI	PSI	PSI		
265	1	8668		-3.80		1.434	0.976	457						
	3	8324	-344	-3.05	+0.75									
	4	9047	+723	-3.81	-0.76									
	5	9636	+589	-4.37	-0.56									
	6	9957	+321	-4.56	-0.19									
	7	11021	+1064	-5.37	-0.81									
186	1	10977		1.16		1.745	2.166	342.5	6291		5068			
	3	8566	-2411	3.87	+2.71				4908	-1383	3955	-1113		
	4	10693	+2127	1.96	-1.91				6128	+1220	4937	+ 982		
	5	12324	+1631	2.41	+0.45				7062	+ 934	5690	+ 753		
	6	13175	+ 851	2.20	-0.21				7550	+ 488	6083	+ 393		
	7	15678	+2503	2.53	+0.33				8985	+1435	7238	+1155		
87	1	5290		3.25		1.495	1.404	423						
	3	4752	-538	2.11	-1.14									
	4	5222	+470	2.83	+0.72									
	5	5525	+303	3.14	+0.31									
	6	5636	+111	3.14	0									
	7	5957	+321	3.38	+0.24									

Nomenclature

M_b = vertical bending moment
 ΔM_b = change in M_b
 F_s = vertical shear force
 ΔF_s = change in F_s
 Z_T = section modulus, top

Z_b = section modulus, bottom
n.a. = neutral axis
 σ_T = vertical bending stress, top
 $\Delta \sigma_T$ = change in σ_T
 σ_B = vertical bending stress, bottom
 $\Delta \sigma_B$ = change in σ_B

TABLE X

SEA-LAND McLEAN CALIBRATION RESULTS
ABS TORSIONAL MOMENTS FOR EACH HATCH AT EACH LOAD CONDITION

H# LC	15	14	13	12	11	10		9	8	7	6	5	4	3	2	1
1	126	666	-930	714	222	27		1057	614	42	454	37	-2930	784	531	-364
	126	792	-138	576	798	825		1882	2496	2538	2992	3029	99	883	1414	1050
3	-25	0	-931	-4	222	27		1057	614	42	454	37	-3316	0	17	-364
	-25	-25	-956	-960	-738	-711		346	960	1002	1456	1493	-1823	-1823	-1806	-2170
4	-25	0	-931	-4	222	0		539	1897	42	944	39	-3316	0	17	-364
	-25	-25	-956	-960	-738	-738		-199	1698	1740	2684	2723	-593	-593	-576	-940
5	667	-863	4680	-1031	11813	-1027		17234	672	-1418	-82	-11873	-4124	-635	-2148	-825
	667	-196	4484	3453	15266	14239		31473	32145	17964	17882	6009	1885	1250	-898	-1723
6	667	-863	4680	2787	11813	-1027		17234	17233	14181	-9157	-11873	-6776	-635	-3450	-2291
	667	-196	4484	7271	19084	18057		35291	52524	38343	29186	17313	10537	9902	6452	4161
7	0	0	0	0	0	0		0	0	0	0	0	0	0	0	0
	0	0	0	0	0	0		0	0	0	0	0	0	0	0	0

666 ← TOP NUMBER IS THE TORSIONAL MOMENT (TON-FT) CONTRIBUTION FOR THE HATCH
792 ← BOTTOM NUMBER IS THE ACCUMULATIVE TORSIONAL MOMENT FOR THE HATCH AS THE CONTRIBUTIONS ARE SUMMED AFT TO FORWARD





Figure 1 INSTRUMENTATION FLOW DIAGRAM



LEGEND

- ⊕ Bidirectional Accelerometer
- Pitch & Roll Pendulum
- ▣ Longitudinal Vertical Bending Element
- ∇ Torstional Shear Cage
- < Shear Gage
- ⋈ Longitudinal Stress Gage
- △ Transverse Girder Gage
- ⊙ Three Arm Rosette
- ∧ Midship Torstional Shear Element
- ▣ Longitudinal Horizontal Bending
- ⋈ Hull Longitudinal Strain

Figure 2 GENERAL SENSOR LAYOUT






Figure 3

DETAILS OF STRAIN GAGE LAYOUT

 Container In Place
 Container Removed




Figure 4-a

CONDITION NO. 3 CONTAINER LOADING
 (Maximum change in hogging moment)




Figure 4-b

CONDITION NO. 4 CONTAINER LOADING
 (All above deck containers removed)




Figure 4-c

CONDITION NO. 5 CONTAINER LOADING
(Partial torsion)










Figure 4-d
CONDITION NO. 6 CONTAINER LOADING
(Full torsion)



— VERTICAL BENDING MOMENT
 VERTICAL SHEAR FORCE
 - - - - TORSIONAL MOMENT






Figure 6
STRESS VS. LOAD CONDITION
ROSETTES AR1 AND AR2




Figure 7
STRESS VS. LOAD CONDITION
ROSETTES R1 AND R2










Figure 8
REPRESENTATION OF STRAIN GAGE DATA
MIDSHIP TRANSVERSE GIRDER






Figure 10
LONGITUDINAL VERTICAL BENDING MIDSHIP (LVB)
MEASURED STRESS VS. CALCULATED STRESS




Figure 11
 LONGITUDINAL STRESSES (MIDSHIP)
 CALCULATED AND MEASURED DATA
 VS. LOAD CONDITION




Figure 12
COMPARISON OF DATA FROM
SCRATCH GAGES AND LST GAGES




Figure 13
MEASURED TORSIONAL SHEAR MIDSHIP (TSM)
AND LONGITUDINAL HORIZONTAL BENDING (LHB)
AND CALCULATED TORSIONAL MOMENT
VS. LOAD CONDITION




Figure 14
STARBOARD BOXGIRDER SHEAR (MIDSHIP)
CALCULATED AND MEASURED DATA
VS. LOAD CONDITION




Figure 15
FORWARD SHEAR STRESS (SFP AND SFS)
CALCULATED AND MEASURED DATA
VS. LOAD CONDITION




Figure 16
AFT SHEAR STRESS (SAP AND SAS)
CALCULATED AND MEASURED DATA
VS. LOAD CONDITION

UNCLASSIFIED

Security Classification

DOCUMENT CONTROL DATA - R & D		
<i>(Security classification of title, body of abstract and indexing annotation must be entered when the overall report is classified)</i>		
1. ORIGINATING ACTIVITY (Corporate author)		2a. REPORT SECURITY CLASSIFICATION
Naval Ship Engineering Center		UNCLASSIFIED
		2b. GROUP
3. REPORT TITLE		
STATIC STRUCTURAL CALIBRATION OF SHIP RESPONSE INSTRUMENTATION SYSTEM ABOARD THE SEA-LAND McLEAN		
4. DESCRIPTIVE NOTES (Type of report and inclusive dates)		
Technical Report		
5. AUTHOR(S) (First name, middle initial, last name)		
R. R. Boentgen and J. W. Wheaton		
6. REPORT DATE	7a. TOTAL NO. OF PAGES	7b. NO. OF REFS
1976	67	2
8a. CONTRACT OR GRANT NO.	9a. ORIGINATOR'S REPORT NUMBER(S)	
b. PROJECT NO. N00024-75-C-4354 SR-211		
c.	9b. OTHER REPORT NO(S) (Any other numbers that may be assigned this report)	
d.	SSC-263	
10. DISTRIBUTION STATEMENT		
This document has been approved for public release and sale; its distribution is unlimited.		
11. SUPPLEMENTARY NOTES		12. SPONSORING MILITARY ACTIVITY
		Naval Sea Systems Command
13. ABSTRACT		
<p>This document reports the results of the calibration of the strain gage portion of the ship response instrumentation installed on the SEA-LAND McLEAN SL-7 class containership. The calibration consisted of a succession of loading conditions achieved by selectively removing container cargo, and was performed on April 9-10, 1973 in Rotterdam. The measured stress changes are compared with calculated predictions, and the results are discussed. In general, the measurements and calculations agree substantially within tolerances assignable to physical conditions.</p>		

SHIP RESEARCH COMMITTEE
Maritime Transportation Research Board
National Academy of Sciences-National Research Council

The Ship Research Committee has technical cognizance of the interagency Ship Structure Committee's research program:

PROF. J. E. GOLDBERG, Chairman, *Professor Emeritus, Purdue University*
MR. D. P. COURTSAL, *General Manager, Engrg. Works Division, DRAVO Corp.*
MR. E. S. DILLON, *Consultant, Silver Spring, Md.*
DEAN D. C. DRUCKER, *College of Engineering, University of Illinois*
MR. G. E. KAMPSCHAEFER, Jr., *Manager, Technical Services, ARMCO Steel Corp.*
PROF. L. LANDWEBER, *Inst. of Hydraulic Research, The University of Iowa*
MR. O. H. OAKLEY, *Consultant, McLean, Virginia*
MR. D. P. ROSEMAN, *Chief Naval Architect, Hydronautics, Inc.*
DEAN R. D. STOUT, *Graduate School, Lehigh University*
MR. R. W. RUMKE, *Executive Secretary, Ship Research Committee*

The Ship Design, Response, and Load Criteria Advisory Group prepared the project prospectus and evaluated the proposals for this project:

MR. D. P. ROSEMAN, Chairman, *Chief Naval Architect, Hydronautics, Inc.*
MR. M. D. BURKHART, *Head, Marine Science Affairs, Dept. of Navy*
DR. D. D. KANA, *Manager, Structural Dynamics & Acoustics, S.W. Res. Inst.*
MR. W. J. LANE, *Structural Engineer, Bethlehem Steel Corp.*
DR. M. K. OCHI, *Research Scientist, Naval Ship Research & Dev. Center*
PROF. W. D. PILKEY, *Department of Mechanics, University of Virginia*
PROF. J. C. SAMUELS, *Dept. of Electrical Engineering, Howard University*
PROF. M. SHINOZUKA, *Dept. of Civil Engineering, Columbia University*
MR. H. S. TOWNSEND, *Consultant, Westport, Conn.*
PROF. G. A. WEMPNER, *School of Engrg. Science & Mechanics, Georgia Inst. of Technology*

The SL-7 Program Advisory Committee provided the liaison technical guidance, and reviewed the project reports with the investigator:

MR. R. C. STRASSER, Chairman, *Consultant, Newport News, Va.*
MR. E. R. ASHEY, *Asst. for Advanced Technology, Naval Ship Engrg. Center*
PROF. J. E. GOLDBERG, *Professor Emeritus, Purdue University*
PROF. E. V. LEWIS, *Director of Research, Webb Inst. of Naval Architecture*
MR. J. H. ROBINSON, *Staff Naval Architect, Naval Ship Res. & Dev. Center*
MR. D. P. ROSEMAN, *Chief Naval Architect, Hydronautics, Inc.*
PROF. R. A. YAGLE, *Dept. of Naval Architecture, University of Michigan*

SHIP STRUCTURE COMMITTEE PUBLICATIONS

These documents are distributed by the National Technical Information Service, Springfield, Va. 22151. These documents have been announced in the Clearinghouse journal U.S. Government Research & Development Reports (USGRDR) under the indicated AD numbers.

- SSC-257, *SL-7 Instrumentation Program Background and Research Plan* by W. J. Siekierka, R. A. Johnson, and CDR C. S. Loosmore, USCG. 1976. AD-A021337.
- SSC-258, *A Study To Obtain Verification of Liquid Natural Gas (LNG) Tank Loading Criteria* by R. L. Bass, J. C. Hokanson, and P. A. Cox. 1976. AD-A025716.
- SSC-259, *Verification of the Rigid Vinyl Modeling Technique: The SL-7 Structure* by J. L. Rodd. 1976. AD-A025717.
- SSC-260, *A Survey of Fastening Techniques for Shipbuilding* by N. Yutani and T. L. Reynolds. 1976.
- SSC-261, *Preventing Delayed Cracks in Ship Welds - Part I* by H. W. Mishler. 1976.
- SSC-262, *Preventing Delayed Cracks in Ship Welds - Part II* by H. W. Mishler. 1976.
- SSC-263, *Static Structural Calibration of Ship Response Instrumentation System Aboard the Sea-Land McLean* by R. R. Boentgen and J. W. Wheaton. 1976.

SL-7 PUBLICATIONS TO DATE

- SL-7-1, (SSC-238) - *Design and Installation of a Ship Response Instrumentation System Aboard the SL-7 Class Containership S.S. SEA-LAND McLEAN* by R. A. Fain. 1974. AD 780090.
- SL-7-2, (SSC-239) - *Wave Loads in a Model of the SL-7 Containership Running at Oblique Headings in Regular Waves* by J. F. Dalzell and M. J. Chiocco. 1974. AD 780065.
- SL-7-3, (SSC-243) - *Structural Analysis of SL-7 Containership Under Combined Loading of Vertical, Lateral and Torsional Moments Using Finite Element Techniques* by A. M. Elbatouti, D. Liu, and H. Y. Jan. 1974. AD-A 002620.
- SL-7-4, (SSC-246) - *Theoretical Estimates of Wave Loads on the SL-7 Containership in Regular and Irregular Seas* by P. Kaplan, T. P. Sargent, and J. Cilmi. 1974. AD-A 004554.
- SL-7-5, (SSC-257) - *SL-7 Instrumentation Program Background and Research Plan* by W. J. Siekierka, R. A. Johnson, and CDR C. S. Loosmore, USCG. 1976. AD-A021337.
- SL-7-6, (SSC-259) - *Verification of the Rigid Vinyl Modeling Techniques: The SL-7 Structure* by J. L. Rodd. 1976. AD-A025717.
- SL-7-7, (SSC-263) - *Static Structural Calibration of Ship Response Instrumentation System Aboard the SEA-LAND McLEAN* by R. R. Boentgen and J. W. Wheaton. 1976.